Pokhara Metropolitan City
Office of Municipal Executive
Kaski

Final Summary of Rates for roads(2082/083) for contract

S.N.	Norms No	Specification Clause No.	Description	Unit	Rate (NRs.)
1	2.1.I.ii A	201	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a **lead of 30 meters** including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Mechanical Means In area of **light jungle** (less than 15 number per 100 sqm)	Sqm	6.11
2	2.1.I.ii B	201	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a **lead of 30 meters** including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Mechanical Means In area of **thorny jungle** (more than 15 number per 100 sqm)	Sqm	6.40
3	2.1.I.ii C	201	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, **up to a lead of 30 meters** including removal and disposal of top organic soil not exceeding 150 mm in thickness. **By Mechanical Means Felling and uprooting of bamboo clearing the area, stacking of bamboo and disposing of wastes**	Sqm	472.48
4	2.1.II.ii A	201	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a **lead of 1000 meters** including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Mechanical Means In area of **light jungle** (less than 15 number per 100 sqm)	Sqm	8.12
5	2.1.II.ii B	201	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a **lead of 1000 meters** including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Mechanical Means In area of **thorny jungle** (more than 15 number per 100 sqm)	Sqm	8.51
6	2.1.II.ii C	201	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, **up to a lead of 1000 meters** including removal and disposal of top organic soil not exceeding 150 mm in thickness. **By Mechanical Means Felling and uprooting of bamboo clearing the area, stacking of bamboo and disposing of wastes**	Cum	880.80

Final Summary of Rates for roads(2082/083) for contract					
S.N.	**Norms No**	**Specification Clause No.**	**Description**	**Unit**	**Rate (NRs.)**
7	2.2 I	201	Cutting of Trees, including cutting of Trunks, Branches andRemoval Cutting of trees, including cutting of trunks, branches and removal of stumps, roots, stacking of serviceable Material withall lifts and up to a lead of 1000 meters and earth filling in the depression/pit. Girth from **300mm to 600mm**	Nos	1,122.14
8	2.2 II	201	Cutting of Trees, including cutting of Trunks, Branches andRemoval Cutting of trees, including cutting of trunks, branches and removal of stumps, roots, stacking of serviceable Material withall lifts and up to a lead of 1000 meters and earth filling in the depression/pit. Girth from **600mm to 900mm**	Nos	3,366.43
9	2.2 III	201	**Cutting of Trees**, including cutting of Trunks, Branches andRemoval Cutting of trees, including cutting of trunks, branches and removal of stumps, roots, stacking of serviceable Material withall lifts and up to a lead of 1000 meters and earth filling in the depression/pit. **Girth from 900mm to 1800mm**	Nos	8,699.35
10	2.2 IV	201	**Cutting of Trees**, including cutting of Trunks, Branches andRemoval Cutting of trees, including cutting of trunks, branches and removal of stumps, roots, stacking of serviceable Material withall lifts and up to a lead of 1000 meters and earth filling in the depression/pit. **Girth from 1800mm to 2500mm**	Nos	20,273.51
11	2.2 V	201	**Cutting of Trees**, including cutting of Trunks, Branches andRemoval Cutting of trees, including cutting of trunks, branches and removal of stumps, roots, stacking of serviceable Material withall lifts and up to a lead of 1000 meters and earth filling in the depression/pit. **Girth above 2500mm**	Nos	67,328.54
12	2.3	201	**Clearing Grass** and Removal of Rubbish and Dressing and levelling the construction surface Clearing Grass/top soil and removal upto 50 m outside the periphery of the area, including cutting and filling of small undulations. **By Manual Means**	Sqm	9.83
13	2.4.iiiB	202	**Dismantling of existing structures** like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including scaffolding wherever necessary, sorting the dismantled Material, disposal of unserviceable Material and stacking the serviceable Material with all lifts and lead of 1000 meters. **Rubble stone masonry in cement mortar.** BY ~~Mechanical Means~~ Manual means.	Cum	2,031.28
14	2.4.iiiF	202	**Dismantling boulders** laid in wire crates including opening of crates and stacking dismantled Material	Cum	1,261.45
15	2.4.ix A	202	**Removing all type of Hume Pipes** and Stacking within a lead of 50 metres including Earthwork and Dismantling of Masonry Works. Up to 600 mm Dia	m	631.35
16	2.4.ix B	202	**Removing all type of Hume Pipes** and Stacking within a lead of 50 metres including Earthwork and Dismantling of Masonry Works. Dia above 600 to 900 mm	m	926.33
17	2.4.ix C	202	**Removing all type of Hume Pipes** and Stacking within a lead of 50 metres including Earthwork and Dismantling of Masonry Works. Dia above 900 mm	m	1,319.63

Final Summary of Rates for roads(2082/083) for contract					
S.N.	**Norms No**	**Specification Clause No.**	**Description**	**Unit**	**Rate (NRs.)**
18	2.5 II A	202	**Dismantling of flexible pavement** and disposal of dismantled material upto a lead of 1000 metres, stacking serviceable and unserviceable Material Separately By Mechanical Means. Bituminuous Course	Cum	1,420.63
19	2.6	202	**Dismantling of cement concrete pavement** by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled Material up to a lead of 1000 metres, stacking serviceable and unserviceable Material separately	Cum	4,913.89
20	2.14	202	**Removal of Telephone/Electric Poles** including excavation and dismantling of foundation concrete and lines under the supervision of concerned departments, disposal with all lifts and up to a lead of 1000 metres and stacking the serviceable and unserviceable material separately.	Nos	934.12
21	7.1 A	701	**Providing, jointing and laying HDPE pipes** with or without collare etc complete in place as per drawing and technical specification **(110/ 125 mm outer dia)**	m	899.76
22		701	**Providing and Laying Reinforced Cement Concrete Flush jointed Pipe for culverts** Providing and Laying Reinforced cement concrete NP3 Flush jointed pipe for culverts including fixing cement mortar 1:2 as per Drawing and Technical Specifications.		
a	7.2 B	701	**300 mm internal Dia**	m	4,291.69
b	7.2 B	701	**450 mm internal Dia**	m	5,849.11
c	7.2 C	701	**600 mm internal Dia**	m	7,860.20
d	7.2 D	701	**900 mm internal Dia**	m	13,906.09
23	9.1	905	**Road way Excavation** as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per		
a	9.1 I B	905	**In all type of soil**	Cum	88.69
b	9.1 II B	905	**Ordinary Rock**	Cum	266.08
c	9.1 IV A	905	**Hard Rock without Blasting only Cutting**	Cum	2,425.77
d			**Hard Rock without Blasting with Deduction Stone**	Cum	2,425.77
e	9.1 III A	905	**Hard Rock with Blasting**	Cum	1,436.86
24	9.2	905	**Removal of Unserviceable** soil including excavation, loading and disposal up to **1000 m** lead	Cum	190.88
25		907	**Earth work in excavation of foundation of structures**, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications. **Ordinary soil Mechanical Means**		
a	9.4 B i		**Depth upto 3 M**	Cum	133.04
b	9.4 B ii		**Depth 3-6 M**	Cum	163.45
c	9.4 B iii		**Depth Above 6 M**	Cum	209.67

Final Summary of Rates for roads(2082/083) for contract					
S.N.	Norms No	Specification Clause No.	Description	Unit	Rate (NRs.)
26	9.4 II B	907	**Earth work in excavation of foundation of structures,** including construction of shoring andbracing, removal of stumps and other deleteriousmatter and backfilling with approved Material asper Drawing and Technical Specifications. **Ordinary Rock**	Cum	390.25
27	9.4 IV A	907	**Earth work in excavation of foundation of structures,** including construction of shoring and bracing, removal of stumps and other deleteriousmatter and backfilling with approved Material as per Drawing and Technical Specifications. **Hard Rock**	Cum	2,122.77
28	9.7	909,910	**Preparation and Surface Treatment of formation** by removing mud and slurry, watering to the extent needed to maintain desire moisture content compacting all complete as per drawing and technical specification	Sqm	9.52
29	9.8	909,910	**Construction of Embankment with Material obtained from borrow pits** Providing, Laying, Spreading and Compacting embankment with borrow material as per Drawing and Technical Specification	Cum	473.44
30	9.9	909,910	**Construction of Embankment with Material deposited from roadway** cutting Providing, Laying, Spreading and Compacting embankment withdeposited material as per Drawing and Technical Specification	Cum	392.73
31	9.11 A	908	**Providing Granular Material and back filling** behind abutment, wing wall and return wall complete as per Drawing and Techinical Specifications.	Cum	1,653.46
32	9.11 B	908	**Providing Sandy Material and back filling** behind abutment, wing wall and return wall complete as per Drawing and Techinical Specifications.	Cum	4,118.60
33	9.11 C	908	**Providing Locally available Material including compaction by tamping rod (without watering) and back filling** behind abutment, wing wall and return wall complete as per Drawing and Techinical Specifications.	Cum	627.58
34	9.12	909, 910	**Providing and Laying of Filter media with grannular Material/stone crushed aggregates** to a thickness of not less than 600 mm with smaller size towards the soil and bigger size towards the wall and provided over the entire surface behind abutement, wing wall and return wall to the full height compacted to a firm condition complete as per drawing and Technical specification.	Cum	4,205.95
35	10.1 A	1003	**Scarifying the existing road surface** to a depth of 50 mm and disposal of scarified Material with all lifts and leads as per Drawing and Technical Specifications. **By Manual Means**	Sqm	42.05
36	10.1 B	1003	**Scarifying the existing granular road surface to a depth of 50 mm** and disposal of scarified Material with all lifts and leads within Right of way as per Drawing and Technical Specifications by Manual means lead up to 30 m	Sqm	21.99
37	10.1 A	1003	**Scarifying the existing road surface** to a depth of 50 mm and disposal of scarified Material with all lifts and leads as per Drawing and Technical Specifications. **By Mechanical Means lead up to 30 m**	Sqm	27.30
38	10.2 B	1003	**Scarifying the existing granular road surface** to a depth of 50 mm and disposal of scarified Material with all lifts and leads within Right of way as per Drawing and Technical Specifications by **Mechanical means**	Sqm	16.95
39	10.4 i	1003, 1005	**Compacting original ground supporting sub-grade** Loosening of the ground upto a level of **500 mm below** the sub-grade level, watered, graded and compacted in layers as per Drawing and Technical Specifications.	Sqm	31.11
40	10.4 ii	1003, 1005	**Compacting original ground supporting embankment Loosening,** leveling and Compacting original ground supporting embankment to facilitate placement of first layer of embankment, scarified to a **depth of 150 mm,** mixed with water at OMC and then compacted by rolling so as to achieve dry density as per Drawing and Technical Specifications.	Cum	93.28

Final Summary of Rates for roads(2082/083) for contract					
S.N.	Norms No	Specification Clause No.	Description	Unit	Rate (NRs.)
41	10.8	1006	Providing and laying of hand pack Stone soling and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	Cum	4,535.72
42	14.1	1401	Providing and Lyaing of **M20 Precast Cement Concrete Kerb 38 cm * 20 cm * 25 cm (H*B*L)** with 12 mm thick 1:3 cement sand mortar bedding and joints including foundation excavation levelling but excluding foundation concrete for foundation or sand gravel material, all complete as per Drawing and Technical Specifications.	m	1,835.25
43	14.2 A	1401	Providing and Laying of **precast / cast in situ 50 mm thick cement concrete slab** footpath on 12mm thick 1:3 cement sand mortar over the prepared base, all complete as per Drawing and Technical Specifications.	Sqm	2,588.35
44	14.2 B	1401	Providing and laying **50 mm thick Natural stone slab** footpath on 12 mm thick 1:3 cement sand mortar over the prepared base, all complete as per specification.	Sqm	2,159.06
45	14.5 A	1403	Providing and laying **brick on edge over 60 mm thick sand bed** in footpath including excavation sand bedding all complete as per Drawing and Technical Specifications.	Sqm	2,105.68
46	14.5 B	1403	Providing and laying **flat brick on edge over 60 mm thick sand bed** in footpath including excavation sand bedding all complete as per Specification.	Sqm	1,230.68
47	26.3 A	2602, 2603, 2607	Providing and laying Random rubble stone masonry in cement mortar [cement(1) : sand(4)] in Foundation complete as per drawing and technical specification. Manual Mixed Mortar	Cum	10,779.46
48	26.3 B	2602, 2603, 2607	Providing and laying Random rubble stone masonry in cement mortar [cement(1) : sand(4)] in Foundation complete as per drawing and technical specification. Machine Mixed Mortar	Cum	9,703.28
49	26.3 C	2602, 2603, 2607	Providing and laying Random rubble stone masonry in cement mortar [cement(1) : sand(6)] in Foundation complete as per drawing and technical specification.	Cum	10,198.27
50	26.5 A	2600, 2607	Providing and laying **Random rubble stone masonry** in cement mortar **[cement(1) : sand(4)]** in **Structure** complete as per drawing and technical specification	Cum	12,502.37
51	26.6 A	2600, 2607	Providing and laying **Random rubble stone masonry** in cement mortar **[cement(1) : sand(6)]** in **Structure** complete as per drawing and technical specification	Cum	11,988.64
52					
53	18.1	1804, 1805	Providing , Preparing and Installing **form work** including necessary supports and removing after completion for foundation and footings (a) using timber (soft wood) - Class F1 finish.	Sqm	765.51
54		1804, 1805	Providing , Preparing and Installing **form work** including necessary supports and removing after completion ---For Vertical plain surface [class F2 finish]		
a	18.2 a i		**height upto 3 m**	Sqm	856.85
b	18.2 a ii		**Height 3-6 m**	Sqm	1,028.48
c	18.2 a iii		**Height 6-9 m**	Sqm	1,287.04
d		1804, 1805	Providing , Preparing and Installing form work including necessary supports and removing after completion ---For Vertical curved surface [class F2 finish]		
e	18.3 a i		**height upto 3.0 m.**	Sqm	856.85
f	18.3 a ii		**Height 3-6 m**	Sqm	1,028.48
g	18.3 a iii		**Height 6-9 m**	Sqm	1,287.04
55	18.6 a	1804, 1805	Providing , Preparing and Installing form work including necessary supports and removing after completion ---For slab structure [class F2 finish] using timber planks. (Falsework not included)	Sqm	992.84

Final Summary of Rates for roads(2082/083) for contract					
S.N.	Norms No	Specification Clause No.	Description	Unit	Rate (NRs.)
56	18.7 a	1804, 1805	Providing , Preparing and Installing form work including necessary supports and removing after completion ---For slab and beam structure [class F2 finish] using timber planks. (Falsework not included)	Sqm	1,469.48
57	18.10 a ii	1804, 1805	Providing, and assembling in position falsework for the construction of RCC superstructure and removal after completion including necessary design and drawings as per specification. A) For Slabs and Box culverts , using timber for height 2m ~ 4m	Sqm	4,956.79
58	18.11 a ii	1804, 1805	Providing, and assembling in position falsework for the construction of RCC superstructure and removal after completion including necessary design and drawings as per specification. A) For RCC beam bridges , using timber for height 3m ~ 6m	Sqm	9,784.88
59	24.21 A(I)	2421	Providing and laying Plum Concrete (Boulder Mixed Concrete) as per Drawing and Specifications 60% M15 concrete and 40% boulders/stone using Mechanical Means.(including formworks)	Cum	9,967.55
60	20.1	2000	Providing and placing machine mixed M10(or 1:3:6 for nominal mix) cement concrete for the foundation and footing etc. including compaction, curing, testing and lead 30m. etc. all complete as per specification and drawing.	Cum	9,413.44
61	20.1	2000	Providing and placing M10 (or 1:3:6 for nominal mix) cement concrete for the foundation and footing etc. including compaction, curing, testing and lead 30m. etc. all complete as per specification and drawing. Manual Method	Cum	9,307.77
62	20.2 A	2000	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M15 (Including Formwork) Manual	Cum	11,381.23
63	20.2 A i	2000	Providing and laying of Machine mixed Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M15 (Including Formwork)	Cum	11,169.99
64	20.2 B	2000	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. PCC Grade M20 (Including Formwork)	Cum	12,292.17
65	20.2 C	2000	Providing and laying of Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications.RCC Grade M20 (Including Formwork)	Cum	12,357.61
66	20.2 D	2000	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. PCC Grade M25 (Including Formwork)	Cum	13,184.74
67	20.2 E	2000	Providing and laying of Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. RCC Grade M25 (Including Formwork)	Cum	13,791.94
68	20.2 F	2000	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. PCC Grade M30 (Including Formwork)	Cum	13,249.37
69	20.2 G	2000	Providing and laying of Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. RCC Grade M30 (Including Formwork)	Cum	13,816.84
70	20.2 H	2000	Providing and laying of Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. RCC Grade M35 (Including Formwork)	Cum	14,016.21

Final Summary of Rates for roads(2082/083) for contract					
S.N.	Norms No	Specification Clause No.	Description	Unit	Rate (NRs.)
71	20.4 E(P)	2000	Providing and laying of Reinforced Cement Concrete in Sub-structure complete as per Drawing and Technical Specifications. RCC Grade M20 Height upto 5 m (Including Formwork)	Cum	13,070.55
72	20.4 E(q)	2000	Providing and laying of Reinforced Cement Concrete in Sub-structure complete as per Drawing and Technical Specifications. RCC Grade M20 Height above 5 to 10m (Including Formwork)	Cum	13,545.85
73	20.4 F(p)	2000	Providing and laying of Reinforced Cement Concrete in Sub-structure complete as per Drawing and Technical Specifications. Grade M25 Height upto 5 m (Including Formwork)	Cum	14,622.78
74	20.4 F(q)	2000	Providing and laying of Reinforced Cement Concrete in Sub-structure complete as per Drawing and Technical Specifications. RCC Grade M25 Height Above 5m to 10m (Including Formwork).	Cum	15,154.52
75	20.4 G (p)	2000	Providing and laying of Reinforced Cement Concrete in Sub-structure complete as per Drawing and Technical Specifications. RCC Grade M30 Height upto 5 m (Including Formwork)	Cum	14,684.56
76	20.4 G (q)	2000	Providing and laying of Reinforced Cement Concrete in Sub-structure complete as per Drawing and Technical Specifications. Grade M30 Height above 5 m to 10m(including formworks)	Cum	15,218.55
77	20.5	2014	Providing and laying , fitting and placing HYSD bar reinforcement in sub-structure complete as per Drawing and Technical Specifications	Kg	130.57
78	20.8 A (i) (p)	2000	Providing and laying of Reinforced / Pre-stressed Cement Concrete in Solid slab Super Structure as per Drawing and Technical Specifications. RCC Grade M20 Height upto 5m (including formworks)	Cum	14,155.86
79	20.8 B (i)(q)	2000	Providing and laying of Reinforced / Pre-stressed Cement Concrete in Solid Slab Super Structure as per Drawing and Technical Specifications. RCC Grade M25 Height above 5 to 10m (including formworks)	Cum	16,532.55
80	20.8 B (i)(r)	2000	Providing and laying of Reinforced / Pre-stressed Cement Concrete in Solid Slab Super Structure as per Drawing and Technical Specifications. RCC Grade M25 Height above 10m (Including Formworks)	Cum	17,193.85
81	20.9	2014	Providing and laying , fitting and placing HYSD bar reinforcement in super-structure complete as per Drawing and Technical Specifications	Kg	133.52
82	24.3	2401, 2402	Supply of machine made hexagonal mesh type 100mm x 120 mm Gabion boxes / mattresses with diapharagms, with binding wire x swg, mesh wire 3mm and selvedged wire 3.9 mm and lacing wire 2.4 mm, including palcing in position including stretching, forming compartments; tying with bracing wires and tie wires; tying down the lid complete; and providing and filling stone / boulder in gabion boxes / mattresses etc. including dressing, beding, bonding and all transporation as per specification.	Cum	6,219.48
83	24.5	2404	Providing, laying and fixing of Geo-textile (filter fabrics), lead 30m	Sqm	174.25
84	26.5 A	2600, 2607	Providing and laying Random rubble stone masonry in cement mortar [cement(1) : sand(4)] in Structure complete as per drawing and technical specification	Cus	12,502.37
85	12.1A	1201	**providing and laying granular sub-base on prepared surface,** mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications. By Mechanical Means	Cum	2,166.80

Final Summary of Rates for roads(2082/083) for contract					
S.N.	Norms No	Specification Clause No.	Description	Unit	Rate (NRs.)
86	12.7A	1204	**Crusher Run Macadam Base and Sub Base,Providing and laying Crusher Run Macadam on a prepared surface,** spreading and mixing , watering and compacting to form a layer of sub-base/Base course as per Drawing and Technical Specifications. (53mm maximum size)	Cum	3,247.78
87	12.7A	1204	**Crusher Run Macadam Base and Sub Base,Providing and laying Crusher Run Macadam on a prepared surface,** spreading and mixing , watering and compacting to form a layer of sub-base/Base course as per Drawing and Technical Specifications. (45mm maximum size)	Cum	3,255.85
88	13.1 A	1302	Providing and applying **prime coat** with Hot Bitumen (including cutter) on prepared surface ofgranular base including cleaning of road surface and spraying by **mechanical means** as per Technical Specification .Prime Coat, with MC 30 / 70	Ltr	170.87
89	13.1 B	1302	Providing and applying **prime coat** with Hot Bitumen (including cutter) on prepared surface of granular base including cleaning of road surface and spraying by **manual means** as per Technical Specification .Prime Coat, with MC 30 / 70	Ltr	311.08
90	13.1 C	1302	Providing and applying prime coat with Bitumen emulsion on prepared surface of granular base including cleaning of road surface and spraying primer at specified rate using mechanical means as per Technical Specification. Prime Coat, with Emulsion	Ltr	155.50
91	13.1 D	1302	Providing and applying primer coat with Bitumen emulsion on prepared surface of granular base including cleaning of road surface and spraying primer at specified rate by manual means as per Technical Specification.Prime Coat, with Emulsion	Ltr	264.63
92	13.2 A	1302	Providing and applying tack coat with hot Bitumen at specified rate on the prepared non-bituminous surfaces including cleaning as per Technical Speciation . Tack coat with Bitumen By Mechanical Means	Ltr	149.04
93	13.2 B	1302	Providing and applying tack coat with hot Bitumen at specified rate on the prepared non-bituminous surfaces including cleaning as per Technical Speciation .Tack coat with Bitumen By Manual Means	Ltr	241.47
94	13.7 A i	1303	Providing and laying surface dressing as wearing course in single coat using gravelon a recently applied layer of bituminous binder on prepared surface as per Drawing andTechnical Specifications. Surface Dressing by mechanical means 19 mm Nominal Size Chipping	Sqm	46.23
95	13.7 A ii	1303	Providing and laying surface dressing as wearing course in single coat using gravelon a recently applied layer of bituminous binder on prepared surface as per Drawing andTechnical Specifications. Surface Dressing by mechanical means 13 mm Nominal Size Chipping	Sqm	33.52
96	13.7 A iii	1303	Providing and laying surface dressing as wearing course in single coat using gravelon a recently applied layer of bituminous binder on prepared surface as per Drawing andTechnical Specifications. Surface Dressing by mechanical means 10 mm Nominal Size Chipping	Sqm	27.75
97	13.9 B	1311 (B -i)	Providing and Laying open graded premix carpet of 20 mm thickness composed of 13.2 mm to 5.6 mm aggregates as wearing coarse on a previously prepared base as per drawing and technical specification. Mechanical Method using hot mix plant	Sqm	264.66

Final Summary of Rates for roads(2082/083) for contract					
S.N.	**Norms No**	**Specification Clause No.**	**Description**	**Unit**	**Rate (NRs.)**
98	13.9 A	1311 (A)	Providing and Laying open graded premix carpet of 20 mm thickness composed of 13.2 mm to 5.6 mm aggregates as wearing coarse on a previously prepared base as per drawing and technical specification. Manual Method	Sqm	322.50
99	13.1 (Type A)	1310	Providing and laying of 20 mm thickness composed of 11.2 mm to 0.09 mm (Type A) or 13.2 mm to 0.09 mm (Type B) aggregates using bitumen as wearing course on a previously prepared base , including mixing in a suitable plant as per drawing and technical specifications(Close graded)	sqm	337.10
100	13.6 A	1309	Providing and Laying Bituminous Concrete/Asphat Concrete using crushed aggreagate of specified grading, premix with bituminous binder and filler as per drawing and technical specification.	Cum	21,793.37
101	13.11	1310	Providing and laying seal coat sealing the voids in a bituminous surface as per drawing and technical specification	Sqm	107.24
102	13.12	1310	Providing and Laying Slurry Seal Consisting of a mixture of fine aggreagate, portland cement filler, bituminous emulsion and water on road surface including cleanin of surface mixing of slurry seal in suitable mobile plant, laying and compacting to provide even riding surface as per drawing and technical specification. 3mm thickness	Sqm	121.55
103	20.02 C & 20.04 E		Providing and laying Plum Concrete (Boulder Mixed Concrete) as per Drawing and Specifications 60% M15 concrete and 40% boulders/stone using Mechanical Means.	Cum	9,967.55
104	29.11 A	2903	Filling Pot-holes and Patch Repairs with open-Graded Premix surfacing, 20 mm. Providing required material and repair the the pot holes including removal of failed material, trimming and finishing the surface applying tack coat on the sides and base of excavation , backfilling with hot bituminous Material andcompaction as per Technical Specification and instruction of the Engineer.	Sq.m	445.83
105			**Bioengineering and road safety miscellaneous**		
a	28.08E	2807	Planting rooted grass slips on the slopes <45o including preparation of slips on site. a max of 5 cm depth with metal rod or Operation includes digging planting hole to hard-wood peg, depending on the nature of the soil. The planting drills should be space	Sq.m	600.68
b	28.08F	2807	Planting rooted grass slips on the slopes 45o - 60o including preparation of slips on site. a max of 5 cm depth with metal rod or Operation includes digging planting hole to hard-wood peg, depending on the nature of the soil. The planting drills should be space	Sq.m	701.95
c	28.08 G	2807	Planting rooted grass slips on the slopes > 60o including preparation of slips on site. a max of 5 cm depth with metal rod or Operation includes digging planting hole to hard-wood peg, depending on the nature of the soil. The planting drills should be space	Sc.m	803.23
d	28.2 C	2803	Collection of hardwood for cuttings for planting Material (e.g. assuro, namdi phul, simali)from the sources within of the road. Material to be minimum. 30cm in length and minimum 2 cm in diameter	nos	12.06
e	28.6A	2805	Mulch production by collection and cutting of weeds and other vegetation such as tite pati, banmara etc., within 1 km of the road, and stacking along roadside.	cum	121 53
f	28.6B	2805	Mulch production by collection and cutting of weeds and other vegetation such as tite pati, banmara etc., within 1 km of the road, and stacking along roadside.	cum	121.53

Final Summary of Rates for roads(2082/083) for contract

S.N.	Norms No	Specification Clause No.	Description	Unit	Rate (NRs.)
g	28.9 B	2807	Planting containerized tree and shrub seedlings, including pitting, transplanting, composting and mulching, on slopes < 30o . Pit size 30 cm diameter x depth mix Compost with soil and back fill into pit to 1/4 of the pit volume	nos	38.47
. h	28.9 B	2807	Planting containerized tree and shrub seedlings, including pitting, transplanting, composting and mulching, on slopes 30o . - 40o Pit size 30 cm diameter x depth mix Compost with soil and back fill into pit to 1/4 of the pit volume	nos	45.56
106	15.1	1501	Providing and fixing of non reflective warning , mandatory and informatory sign board of 2mm thick MS sheet with back support frame on heavy 50mm tube or Channel section of 75mm *40mm firmly fixed to the ground by means of properly designed foundation with M 10/40 grade cement concrete 300mm *300mm *300mm as per drawings and Technical specifications /DoR Publication.		
		a)	60 cm equilateral triangle	nos	5,804.53
		b)	60 cm circular	nos	6,409.91
		c)	80cm*60 cm rectangular	nos	7,063.08
107	15.12	1507	Providing and installation of 150 mm * 150 mm 1. 5 m long delineators (road way indicators, hazard markers, object markers), 80-100 cm high above ground level, painted black and white in 20 cm wide strips, buried or pressed into the ground and conforming to the drawings and Technical Specifications.	nos	1,519.51
108	15.11 (i)	1506	Providing and Fixing Reinforced cement concrete M15 grade kilometer Post including painting and printing as per Standard Drawing-2070 and Technical Specifications. Position (I) Five Kilometer Post Precast	nos	10,477.64
109	15.11 (ii)	1506	Providing and Fixing Reinforced cement concrete M15 grade kilometer Post including painting and printing as per Standard Drawing-2070 and Technical Specifications. Position (I) One Kilometer Post Precast	nos	5,918.15
110	15.9 (i)	1504	Providing and laying of Road Marking with Hot Applied Thermoplastic Compound at least 2mm thick including Reflectorizing Glass Beads on Bituminous Surface As per DOR Traffice sign manual/Specification.The finished surface to be level, uniform and free from streaks and holes. (i) (on smooth surface (similar to Asphalt concrete and rigid pavements))	sqm	708.01
111	15.9 (ii)	1504	Providing and laying of Road Marking with Hot Applied Thermoplastic Compound at least 2mm thick including Reflectorizing Glass Beads on Bituminous Surface As per DOR Traffice sign manual/Specification.The finished surface to be level, uniform and free from streaks and holes. (i) (on rough surface (similar to surface dressing))	sqm	1,191.64
112	15.14 (A)	1509	Provide and erecting "W" metal beam crash barrier comprising of 3.00mm thick corrugated sheet metal beam rail, 70cm above road/ground level,fixed on ISMC series channel vertical post, 150*75*5 mm spaced 2m c/c,1.8m high,1.1m below ground/road level,,metal beam rail to be fixed on the vertical post with a spacer of chaneel section 150*75*5mm 330mm long complete as per Drawing and Technical specifications	Rm	9,627.44
113	10.3	1004	Construction of Subgrade and Earthen Shoulders with approved Material (capping layer) Providing and laying sub-grade and earthen shoulders with approved Material obtained from borrow pits with all lifts & leads as per Drawing and Technical Specifications.	cum	1,816.44
114	13.16	1300	Providing and mixing of Anti stripping agent as per Design/ direction of Engineer	kg	665.01
115	24.4	2401	Providing and filling stone/ boulder in gabion boxes/ mattresses etc including dressing, bedding, bonding all complete as per drawing and technical specification	cum	3,871.82

Final Summary of Rates for roads(2082/083) for contract					
S.N.	Norms No	Specification Clause No.	Description	Unit	Rate (NRs.)
116	29.80	2906	Maintenance of Earth Shoulder (stripping excess soil) Strippingexcesssoil from theshoulder surfaceto achieve the approved level and compacting as per Technical Specifications and direction of the Engineer.	sqm	55.49
117	29.19	2,900,900	Land Slide Clearance in soil Clearance of land slides in soil and ordinary rock by machine and disposal of the same on the valley side	cum	53.75
118	29.18	2,900,900	Hill Side Drain Clearance Removal of earth from the choked hill side drain and disposing it on the valley side manually	m	238.05
119	20.2 A	2000	Providing and laying of Machine mixed Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M15 (Excluding Formwork)	cum	10,740.38
120	20.2 A	2000	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M15 (Excluding Formwork) Manual	cum	11,863.35
121	20.2 B	2000	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. PCC Grade M20 (Excluding Formwork)	cum	11,819.39
122	20.2 C	2000	Providing and laying of Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications.RCC Grade M20 (Excluding Formwork)	cum	11,882.32
123		1006	Collection of Stone from near by site/source and laying of hand pack Stone soling and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	cum	3,378.12
124	26.3.b	2602,2603 ,2607	Collection of stone from near by site/source and laying Random rubble stone masonry in cement mortar [cement(1) : sand(4)] in Foundation complete as per drawing and technical specification. Manual Mixed Mortar	cum	9,476.68
125	26.3.b	2602,2603 ,2607	Collection of stone from near by site/source and laying Random rubble stone masonry in cement mortar [cement(1) : sand(4)] in Foundation complete as per drawing and technical specification. Machine Mixed Mortar	cum	8,400.49
126	26.3.C	2602,2603 ,2607	Collection of stone from near by site/source and laying Random rubble stone masonry in cement mortar [cement(1) : sand(6)] in Foundation complete as per drawing and technical specification.	cum	8,895.49
127	26.5 A	2602,2603 ,2607	Collection of stone from near by site/source and laying Random rubble stone masonry in cement mortar [cement(1) : sand(4)] in Structure complete as per drawing and technical specification	cum	11,134.45
128	26.6 A	2602,2603 ,2607	Collection of stone from near by site/source and laying Random rubble stone masonry in cement mortar [cement(1) : sand(6)] in Structure complete as per drawing and technical specification	cum	10,620.72
129	24.21 C	2421	Collection of Stone from near by site/source and laying Plum Concrete (Boulder Mixed Concrete) as per Drawing and Specifications 60% M15 concrete and 40% boulders/stone using Mechanical Means.	cum	9,469.09
131	24.3	2401	Supply of machine made hexagonal mesh type 100mm x 120 mm Gabion boxes / mattresses with diapharagms, with binding wire x swg, mesh wire 3mm and selvedged wire 3.9 mm and lacing wire 2.4 mm, including palcing in position including stretching, forming compartments; tying with bracing wires and tie wires; tying down the lid complete; and collection of stone from nearby side /source and filling stone / boulder in gabion boxes / mattresses etc. including dressing, beding, bonding and all transporation as per specification.		
			1.5*1*1	cum	4,949.14
			2*1*1	cum	5,021.75

Final Summary of Rates for roads(2082/083) for contract					
S.N.	**Norms No**	**Specification Clause No.**	**Description**	**Unit**	**Rate (NRs.)**
			3*1*1	cum	4,949.14
			Uses for estimation	cum	4,973.34
132	24.4	2401	Providing and filling stone/ boulder in gabion boxes/ mattresses etc including dressing, bedding, bonding all complete as per drawing and technical specification	cum	2,625.68
133	15.4	1501	Painting Two Coats on Concrete Surfaces Providing and Painting two coats after filling the surface with synthetic enamel paint in all shades on concrete / plaster surfaces as per Drawing and Technical Specifications.	sqm	946.16
134	15.8	1506	lettering new letter and figures of any shade with synthetic enamel paint black or any other approved color to give an even shade.	cm-letter	4.96