Pokhara Metropolitan city
Office of Municipal Executive

Kaski

RATE ANALYSIS (2082/083)

Description of works:	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a lead of 30 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Mechanical Means in area of light jungle (less than 15 number per 100 sqm)	Unit : 10000 m2
Spec. cl. No: 201		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
2.1.I.ii A	Unskilled	md	6.00	855.00	5130.00						Dozer/Excavator	hr	12.00	3997.47	47969.64
				Sub total of A =	5130.00				Sub total of B =	0.00				Sub total of C =	47969.64
				Sub total of A +B + C =	53099.64				Contractor's overhead expenses 15% =		7964.95			Rate =	61064.59
														Rate per M2	6.11

Description of works:	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a lead of 30 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Mechanical Means in area of thorny jungle (more than 15 number per 100 sqm)	Unit : 10000 m2
Spec. cl. No: 201		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
2.1.I.ii B	Unskilled	md	9.00	855.00	7695.00						Dozer/Excavator	hr	12.00	3997.47	47969.64
				Sub total of A =	7695.00				Sub total of B =	0.00				Sub total of C =	47969.64
				Sub total of A +B + C =	55664.64				Contractor's overhead expenses 15% =		8349.70			Rate =	64014.34
														Rate per m2	6.40

Description of works:	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a lead of 30 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Mechanical Means Felling and uprooting of bamboo clearing the area, stacking of bamboo and disposing of wastes	Unit : 100 Cum
Spec. cl. No: 201		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	?><	Rate	Amount
2.1.I.ii C	Unskilled	md	20.00	855.00	17100.00						Dozer/Excavator	hr	6.00	3997.47	23984.82
				Sub total of A =	17100.00				Sub total of B =	0.00				Sub total of C =	23984.82
				Sub total of A +B + C =	41084.82				Contractor's overhead expenses 15% =		6162.72			Rate =	47247.54
														Rate Per Cum	472.48

RATE ANALYSIS (2082/083)

Description of works:	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Mechanical Means in area of light jungle (less than 15 number per 100 sqm)	Unit : 10000 m2
Spec. cl. No: 201		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
2.1.II.iiA	Unskilled	md	8.00	855.00	6840.00						Dozer/Excavator	hr	12.00	3997.47	47969.64
											Tractor-Trolley	hr	12.00	1316.38	15796.56
				Sub total of A =	6840.00				Sub total of B =	0.00				Sub total of C =	63766.20
				Sub total of A +B + C =	70606.20				Contractor's overhead expenses 15% =		10590.93			Rate =	81197.13
														Rate per M2	8.12

Description of works:	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Mechanical Means in area of thorny jungle (more than 15 number per 100 sqm)	Unit : 10000 m2
Spec. cl. No: 201		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
2.1.II.ii B	Unskilled	md	12.00	855.00	10260.00						Dozer/Excavator	hr	12.00	3997.47	47969.64
											Tractor-Trolley	hr	12.00	1316.38	15796.56
				Sub total of A =	10260.00				Sub total of B =	0.00				Sub total of C =	63766.20
				Sub total of A +B + C =	74026.20				Contractor's overhead expenses 15% =		11103.93			Rate =	85130.13
														Rate per m2	8.51

Description of works:	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Mechanical Means Felling and uprooting ofBAMBOO clearing the area, stacking of BAMBOO and disposing of wastes	Unit : 100 Cum
Spec. cl. No: 201		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
2.1.II.iiC	Unskilled	md	15.00	855.00	12825.00						Dozer/Excavator	hr	12.00	3997.47	47969.64
											Tractor -Trolley	hr	12.00	1316.38	15796.56
				Sub total of A =	12825.00				Sub total of B =	0.00				Sub total of C =	63766.20
				Sub total of A +B + C =	76591.20				Contractor's overhead expenses 15% =		11488.68			Rate =	88079.88
														Rate Per Cum	880.80

Description of works:	Cutting of Trees, including cutting of Trunks, Branches andRemoval Cutting of trees, including cutting of trunks, branches and removal of stumps, roots, stacking of serviceable Material withall lifts and up to a lead of 1000 meters and earth filling in the depression/pit. Girth from 300mm to 600mm	Unit : 30 No.
Spec. cl. No: 201		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
2.2.i	Unskilled	md	25.00	855.00	21375.00						Tractor-trolley	hr	6.00	1316.38	7898.28
				Sub total of A =	21375.00				Sub total of B =	0.00				Sub total of C =	7898.28
				Sub total of A +B + C =	29273.28				Contractor's overhead expenses 15% =		4390.99			Rate =	33664.27
														Rate Per No	1122.14

RATE ANALYSIS (2082/083)

Description of works:	Cutting of Trees, including cutting of Trunks, Branches andRemoval Cutting of trees, including cutting of trunks, branches and removal of stumps, roots, stacking of serviceable Material withall lifts and up to a lead of 1000 meters and earth filling in the depression/pit. Girth from 600mm to 900mm	Unit : 10 No.
Spec. cl. No: 201		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
2.2.ii	Unskilled	md	25.00	855.00	21375.00						Tractor-trolley	hr	6.00	1316.38	7898.28
				Sub total of A =	21375.00				Sub total of B =	0.00				Sub total of C =	7898.28
				Sub total of A +B + C =	29273.28				Contractor's overhead expenses 15% =		4390.99			Rate =	33664.27
														Rate Per No	3366.43

Description of works:	Cutting of Trees, including cutting of Trunks, Branches andRemoval Cutting of trees, including cutting of trunks, branches and removal of stumps, roots, stacking of serviceable Material withall lifts and up to a lead of 1000 meters and earth filling in the depression/pit. Girth from 900mm to 1800mm	Unit : 5 No.
Spec. cl. No: 201		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
2.2.iii	Unskilled	md	35.00	855.00	29925.00						Tractor-trolley	hr	6.00	1316.38	7898.28
				Sub total of A =	29925.00				Sub total of B =	0.00				Sub total of C =	7898.28
				Sub total of A +B + C =	37823.28				Contractor's overhead expenses 15% =		5673.49			Rate =	43496.77
														Rate Per No	8699.35

Description of works:	Cutting of Trees, including cutting of Trunks, Branches andRemoval Cutting of trees, including cutting of trunks, branches and removal of stumps, roots, stacking of serviceable Material withall lifts and up to a lead of 1000 meters and earth filling in the depression/pit. Girth from 1800mm to 2500mm	Unit : 2 No.
Spec. cl. No: 201		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
2.2.iv	Unskilled	md	32.00	855.00	27360.00						Tractor-trolley	hr	6.00	1316.38	7898.28
				Sub total of A =	27360.00				Sub total of B =	0.00				Sub total of C =	7898.28
				Sub total of A +B + C =	35258.28				Contractor's overhead expenses 15% =		5288.74			Rate =	40547.02
														Rate Per No	20273.51

Description of works:	Cutting of Trees, including cutting of Trunks, Branches andRemoval Cutting of trees, including cutting of trunks, branches and removal of stumps, roots, stacking of serviceable Material withall lifts and up to a lead of 1000 meters and earth filling in the depression/pit. Girth above 2500mm	Unit : 1 No.
Spec. cl. No: 201		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
2.2.v	Unskilled	md	50.00	855.00	42750.00						Tractor-trolley	hr	12.00	1316.38	15796.56
				Sub total of A =	42750.00				Sub total of B =	0.00				Sub total of C =	15796.56
				Sub total of A +B + C =	58546.56				Contractor's overhead expenses 15% =		8781.98			Rate =	67328.54

Description of works:	Dressing and levelling of the construction surface including cutting and filling of small undulation.	Unit : 1 m2
Spec. cl. No: 201, 909		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
2.05	Unskilled	md	0.01	855.00	8.55						Tools and plants	%	3.00		0.25
				Sub total of A =	8.55				Sub total of B =	0.00				Sub total of C =	0.25
				Sub total of A +B + C =	8.80				Contractor's overhead expenses 15% =		1.32			Rate =	10.12

RATE ANALYSIS (2082/083)

Description of works:	Excavation of top soil (sub grade) and carrying away from construction site, lead 10m and thickness upto 100mm.	Unit : 1 m2
Spec. cl. No: 201, 1003		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
2.06	Unskilled	md	0.16	855.00	136.80						Tools and plants	%	3.00		4.10
				Sub total of A =	136.80				Sub total of B =	0.00				Sub total of C =	4.10
				Sub total of A +B + C =	140.90				Contractor's overhead expenses 15% =		21.14			Rate =	162.04

Description of works:	Spreading, shaping and light compacting of top soil on slopes.	Unit : 1 m2
Spec. cl. No: 201, 2800		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
2.07	Unskilled	md	0.05	855.00	42.75						Tools and plants	%	3.00		1.28
				Sub total of A =	42.75				Sub total of B =	0.00				Sub total of C =	1.28
				Sub total of A +B + C =	44.03				Contractor's overhead expenses 15% =		6.60			Rate =	50.63

Description of works:	Dismantling Bridge, culvert and other structures including stockpiling the reusable materials and diposal of usable materials within 50 m lead for (a) Plain cement concrete, 1:4:8 or leaner mix	Unit : 1 m3
Spec. cl. No: 202		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
2.08.01	Skilled	md	0.05	1215.00	60.75						Tools and plants	%	3.00		37.73
	Unskilled	md	1.40	855.00	1197.00										
				Sub total of A =	1257.75				Sub total of B =	0.00				Sub total of C =	37.73
				Sub total of A +B + C =	1295.48				Contractor's overhead expenses 15% =		194.32			Rate =	1489.80

Description of works:	Dismantling Bridge, culvert and other structures including stockpiling the reusable materials and diposal of usable materials within 50 m lead for (b) Plain cement concrete, 1:3:6 or richer mix	Unit : 1 m3
Spec. cl. No: 202		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
2.08.02	Skilled	md	0.05	1215.00	60.75						Tools and plants	%	3.00		60.81
	Unskilled	md	2.30	855.00	1966.50										
				Sub total of A =	2027.25				Sub total of B =	0.00				Sub total of C =	60.81
				Sub total of A +B + C =	2088.06				Contractor's overhead expenses 15% =		313.21			Rate =	2401.27

RATE ANALYSIS (2082/083)

Description of works:	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including scaffolding wherever necessary, sorting the dismantled Material, disposal of unserviceable Material and stacking the serviceable Material with all lifts and lead of 1000 meters. Rubble stone masonry in cement mortar. BY ~~Mechanical Means~~ Manual means	Unit : 1 m3
Spec. cl. No: 202		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
2.08.03	Skilled	md	0.05	1215.00	60.75						Tools and plants	%	3.00		85.18
	Unskilled	md	3.25	855.00	2778.75										
				Sub total of A =	2839.50				Sub total of B =	0.00				Sub total of C =	85.18
				Sub total of A +B + C =	2924.68				Contractor's overhead expenses 15% =		438.70			Rate =	3363.38

Description of works:	Clearing Grass and Removal of Rubbish and Dressing and levelling the construction surface Clearing Grass/top soil and removal upto 50 m outside the periphery of the area, including cutting and filling of small undulations. By Manual Means	Unit : 10000 Sqm
Spec. cl. No: 201		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
2.3	Unskilled	md	100.00	855.00	85500.00									0.00	0.00
				Sub total of A =	85500.00				Sub total of B =	0.00				Sub total of C =	0.00
				Sub total of A +B + C =	85500.00				Contractor's overhead expenses 15% =		12825.00			Rate =	98325.00
														Per Sqm	9.83

Description of works:	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including scaffolding wherever necessary, sorting the dismantled Material, disposal of unserviceable Material and stacking the serviceable Material with all lifts and lead of 1000 meters. Rubble stone masonry in cement mortar. BY Mechanical Means	Unit : 10 m3
Spec. cl. No: 202		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
2.4iii B	Skilled	md	1.00	1215.00	1215.00						Tractor-trolley	hr	6.00	1316.38	7898.28
	Unskilled	md	10.00	855.00	8550.00										
				Sub total of A =	9765.00				Sub total of B =	0.00				Sub total of C =	7898.28
				Sub total of A +B + C =	17663.28				Contractor's overhead expenses 15% =		2649.49			Rate =	20312.77
														Rate per M3	2031.28

Description of works:	Dismantling boulders laid in wire crates including opening of crates and stacking dismantled Material	Unit : 20 m3
Spec cl. No: 202		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
2.4 iii F	Skilled	md	1.00	1215.00	1215.00						Tractor -trolley	hr	6.00	1316.38	7898.28
	Unskilled	md	15.00	855.00	12825.00										
				Sub total of A =	14040.00				Sub total of B =	0.00				Sub total of C =	7898.28
				Sub total of A +B + C =	21938.28				Contractor's overhead expenses 15% =		3290.74			Unit Rate =	25229.02
														Unit Per m3	1261.45