# RATE ANALYSIS (2082/083)

| Description of works: | Removing all type of Hume Pipes and Stacking within a lead of 50 metres including Earthwork and Dismantling of Masonry Works. Up to 600 mm Dia | Unit : 10 M |
|---|---|---|
| Spec. cl. No: 202 | | |

| Norms No. | Labour (A) | | | | | Material (B) | | | | | Equipment (C) | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount |
| 2.4.ix A | Skilled | md | 1.00 | 1215.00 | 1215.00 | | | | | | Tools and plant | | | | 0.00 |
| | Unskilled | md | 5.00 | 855.00 | 4275.00 | | | | | | | | | | |
| | | | | Sub total of A = | 5490.00 | | | | Sub total of B = | 0.00 | | | | Sub total of C = | 0.00 |
| | | | | Sub total of A +B + C = | 5490.00 | | | | Contractor's overhead expenses 15% = | | 823.50 | | | Unit Rate = | 6313.50 |
| | | | | | | | | | | | | | | Rate Per M | 631.35 |

| Description of works: | Removing all type of Hume Pipes and Stacking within a lead of 50 metres including Earthwork and Dismantling of Masonry Works. Dia above 600 to 900 mm | Unit : 10 M |
|---|---|---|
| Spec. cl. No: 202 | | |

| Norms No. | Labour (A) | | | | | Material (B) | | | | | Equipment (C) | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount |
| 2.4.ix B | Skilled | md | 1.00 | 1215.00 | 1215.00 | | | | | | | | | | 0.00 |
| | Unskilled | md | 8.00 | 855.00 | 6840.00 | | | | | | | | | | |
| | | | | Sub total of A = | 8055.00 | | | | Sub total of B = | 0.00 | | | | Sub total of C = | 0.00 |
| | | | | Sub total of A +B + C = | 8055.00 | | | | Contractor's overhead expenses 15% = | | 1208.25 | | | Unit Rate = | 9263.25 |
| | | | | | | | | | | | | | | Rate Per M | 926.33 |

| Description of works: | Removing all type of Hume Pipes and Stacking within a lead of 50 metres including Earthwork and Dismantling of Masonry Works. Dia above 900 mm | Unit : 10 M |
|---|---|---|
| Spec. cl. No: 202 | | |

| Norms No. | Labour (A) | | | | | Material (B) | | | | | Equipment (C) | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount |
| 2.4.ix C | Skilled | md | 1.00 | 1215.00 | 1215.00 | | | | | | | | | | 0.00 |
| | Unskilled | md | 12.00 | 855.00 | 10260.00 | | | | | | | | | | |
| | | | | Sub total of A = | 11475.00 | | | | Sub total of B = | 0.00 | | | | Sub total of C = | 0.00 |
| | | | | Sub total of A +B + C = | 11475.00 | | | | Contractor's overhead expenses 15% = | | 1721.25 | | | Unit Rate = | 13196.25 |
| | | | | | | | | | | | | | | Rate Per M | 1319.63 |

| Description of works: | Dismantling of flexible pavement and disposal of dismantled material upto a lead of 1000 metres, stacking serviceable and unserviceable Material Separately By Mechanical Means. Bituminuou Course | Unit :20 m3 |
|---|---|---|
| Spec. cl. No: 202 | | |

| Norms No. | Labour (A) | | | | | Material (B) | | | | | Equipment (C) | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount |
| 2.5 ii A | Skilled | md | 1.00 | 1215.00 | 1215.00 | | | | | | Tractor-trolly | hr | 6.00 | 1316.38 | 7898.28 |
| | Unskilled | md | 9.00 | 855.00 | 7695.00 | | | | | | Tractor with ripper | hr | 6.00 | 1316.38 | 7898.28 |
| | | | | Sub total of A = | 8910.00 | | | | Sub total of B = | 0.00 | | | | Sub total of C = | 15796.56 |
| | | | | Sub total of A +B + C = | 24706.56 | | | | Contractor's overhead expenses 15% = | | 3705.98 | | | Unit Rate = | 28412.54 |
| | | | | | | | | | | | | | | Rate Per M3 | 1420.63 |

# RATE ANALYSIS (2082/083)

| Description of works: | Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled Material up to a lead of 1000 metres, stacking serviceable and unserviceable Material separately | Unit :10 m3 |
|---|---|---|
| Spec. cl. No: 202 | | |

| Norms No. | Labour (A) | | | | | Material (B) | | | | | Equipment (C) | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount |
| 2.6 | Skilled | md | 1.00 | 1215.00 | 1215.00 | | | | | | Tractor-trolly | hr | 6.00 | 1316.38 | 7898.28 |
| | Semi Skilled | md | 8.00 | 1020.00 | 8160.00 | | | | | | Air compressor | hr | 6.00 | 1727.47 | 10364.82 |
| | Unskilled | md | 8.00 | 855.00 | 6840.00 | | | | | | Joint Cutting Machine | hr | 6.00 | 1375.23 | 8251.38 |
| | | | | Sub total of A = | 16215.00 | | | | Sub total of B = | 0.00 | | | | Sub total of C = | 26514.48 |
| | | | | Sub total of A +B + C = | 42729.48 | | | | Contractor's overhead expenses 15% = | | 6409.42 | | | Unit Rate = | 49138.90 |
| | | | | | | | | | | | | | | Rate Per M3= | 4913.89 |

| Description of works: | Removal of Telephone/Electric Poles including excavation and dismantling of foundation concrete and lines under the supervision of concerned departments, disposal with all lifts and up to a lead of 1000 metres and stacking the serviceable and unserviceable material separately. | Unit : 30 Nos |
|---|---|---|
| Spec. cl. No: 202 | | |

| Norms No. | Labour (A) | | | | | Material (B) | | | | | Equipment (C) | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount |
| 2.14 | Skilled | md | 3.00 | 1215.00 | 3645.00 | | | | | | Tractor-trolly | hr | 6.00 | 1316.38 | 7898.28 |
| | Unskilled | md | 15.00 | 855.00 | 12825.00 | | | | | | | | | | |
| | | | | Sub total of A = | 16470.00 | | | | Sub total of B = | 0.00 | | | | Sub total of C = | 7898.28 |
| | | | | Sub total of A +B + C = | 24368.28 | | | | Contractor's overhead expenses 15% = | | 3655.24 | | | Unit Rate = | 28023.52 |
| | | | | | | | | | | | | | | Rate Per Nos= | 934.12 |

| Description of works: | Providing, jointing and laying HDPE pipes with or without collar etc complete in place as per drawing and technical specification (110/ 125 mm outer dia ) | Unit : 50 m |
|---|---|---|
| Spec. cl. No: 701 | | |

| Norms No. | Labour (A) | | | | | Material (B) | | | | | Equipment (C) | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount |
| 7.1.A | Skilled | md | 3.00 | 1215.00 | 3645.00 | HDPE Pipe 110/125 mm | m | 50.0 | 510.90 | 25545.00 | Generator | hr | 6.00 | 1173.44 | 7040.64 |
| | Unskilled | md | 3.00 | 855.00 | 2565.00 | | | | | | Screw Jack | hr | 6.00 | 15 | 90.00 |
| | | | | | | | | | | | Electric Heating Plate | hr | 6.00 | 8 | 48.00 |
| | | | | | | | | | | | 3 % of labor cost for other T & P | | | | 186.3 |
| | | | | Sub total of A = | 6210.00 | | | | Sub total of B = | 25545.00 | | | | Sub total of C = | 7364.94 |
| | | | | Sub total of A +B + C = | 39119.94 | | | | Contractor's overhead expenses 15% = | | 5867.99 | | | Unit Rate = | 44987.93 |
| | | | | | | | | | | | | | | Rate Per M= | 899.76 |

| Description of works: | Providing and Laying Reinforced Cement Concrete Flush jointed Pipe for culverts Providing and Laying Reinforced cement concrete NP3 Flush jointed pipe for culverts including fixing cement mortar 1:2 as per Drawing and Technical Specifications. 300 mm internal Dia | Unit : 12.5 m |
|---|---|---|
| Spec. cl. No: 701 | | |

| Norms No. | Labour (A) | | | | | Material (B) | | | | | Equipment (C) | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount |
| 7.2.A | Skilled | md | 1.00 | 1215.00 | 1215.00 | RCC Pipe | m | 12.5 | 3199.82 | 39997.79 | | | | | |
| | Unskilled | md | 5.00 | 855.00 | 4275.00 | Cement | mt | 0.060 | 13500.00 | 810.00 | 3 % of Labour cost for bellies, crow bars, chain pulley and other T & P | | 0.03 | | 164.70 |
| | | | | | | Sand | $m^3$ | 0.080 | 2329.00 | 186.32 | | | | | |
| | | | | Sub total of A = | 5490.00 | | | | Sub total of B = | 40994.11 | | | | Sub total of C = | 164.70 |
| | | | | Sub total of A +B + C = | 46648.81 | | | | Contractor's overhead expenses 15% = | | 6997.32 | | | Unit Rate = | 53646.13 |
| | | | | | | | | | | | | | | Rate Per M= | 4291.69 |

# RATE ANALYSIS (2082/083)

| Description of works: | Providing and Laying Reinforced Cement Concrete Flush jointed Pipe for culverts Providing and Laying Reinforced cement concrete NP3 Flush jointed pipe for culverts including fixing cement mortar 1:2 as per Drawing and Technical Specifications. 450 mm internal Dia | Unit : 12.5 m |
|---|---|---|
| Spec. cl. No: 701 | | |

| Norms No. | Labour (A) | | | | | Material (B) | | | | | Equipment (C) | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount |
| 7.2.B | Skilled | md | 1.00 | 1215.00 | 1215.00 | RCC Pipe | m | 12.5 | 4470.99 | 55887.34 | 3 % of Labour cost for bellies, crow bars, chain pulley and other T & P | | 0.03 | | 190.35 |
| | Unskilled | md | 6.00 | 855.00 | 5130.00 | Cement | mt | 0.070 | 13500.00 | 945.00 | | | | | |
| | | | | | | Sand | $m^3$ | 0.090 | 2329.00 | 209.61 | | | | | |
| | | | | Sub total of A = | 6345.00 | | | | Sub total of B = | 57041.95 | | | | Sub total of C = | 190.35 |
| | | | | Sub total of A +B + C = | 63577.30 | | | | Contractor's overhead expenses 15% = | | 9536.60 | | | Unit Rate = | 73113.90 |
| | | | | | | | | | | | | | | Rate Per M= | 5849.11 |

| Description of works: | Providing and Laying Reinforced Cement Concrete Flush jointed Pipe for culverts Providing and Laying Reinforced cement concrete NP3 Flush jointed pipe for culverts including fixing cement mortar 1:2 as per Drawing and Technical Specifications. 600 mm internal Dia | Unit : 12.5 m |
|---|---|---|
| Spec. cl. No: 701 | | |

| Norms No. | Labour (A) | | | | | Material (B) | | | | | Equipment (C) | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount |
| 7.2.C | Skilled | md | 1.00 | 1215.00 | 1215.00 | RCC Pipe | m | 12.5 | 6136.65 | 76708.09 | 3 % of Labour cost for bellies, crow bars, chain pulley and other T & P | | 0.03 | | 216.00 |
| | Unskilled | md | 7.00 | 855.00 | 5985.00 | Cement | kg | 0.080 | 13500.00 | 1080.00 | | | | | |
| | | | | | | Sand | $m^3$ | 0.100 | 2329.00 | 232.90 | | | | | |
| | | | | Sub total of A = | 7200.00 | | | | Sub total of B = | 78020.99 | | | | Sub total of C = | 216.00 |
| | | | | Sub total of A +B + C = | 85436.99 | | | | Contractor's overhead expenses 15% = | | 12815.55 | | | Unit Rate = | 98252.54 |
| | | | | | | | | | | | | | | Rate Per M= | 7860.20 |

| Description of works: | Providing and Laying Reinforced Cement Concrete Flush jointed Pipe for culverts Providing and Laying Reinforced cement concrete NP3 Flush jointed pipe for culverts including fixing cement mortar 1:2 as per Drawing and Technical Specifications. 900 mm internal Dia | Unit : 12.5 m |
|---|---|---|
| Spec. cl. No: 701 | | |

| Norms No. | Labour (A) | | | | | Material (B) | | | | | Equipment (C) | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount |
| 7.2.D | Skilled | md | 1.00 | 1215.00 | 1215.00 | RCC Pipe | m | 12.5 | 11308.96 | 141362.00 | 3 % of Labour cost for bellies, crow bars, chain pulley and other T & P | | 0.03 | | 241.65 |
| | Unskilled | md | 8.00 | 855.00 | 6840.00 | Cement | kg | 0.090 | 13500.00 | 1215.00 | | | | | |
| | | | | | | Sand | $m^3$ | 0.120 | 2329.00 | 279.48 | | | | | |
| | | | | Sub total of A = | 8055.00 | | | | Sub total of B = | 142856.48 | | | | Sub total of C = | 241.65 |
| | | | | Sub total of A +B + C = | 151153.13 | | | | Contractor's overhead expenses 15% = | | 22672.97 | | | Unit Rate = | 173826.10 |
| | | | | | | | | | | | | | | Rate Per M= | 13906.09 |

| Description of works: | Road way Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. (Mechanical Means) | Unit : 360 m3 |
|---|---|---|
| Spec. cl. No: 905 | | |

| Norms No. | Labour (A) | | | | | Material (B) | | | | | Equipment (C) | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount |
| 9.1.I.B | Skilled | md | 1.00 | 1215.00 | 1215.00 | | | | | | Hydraulic Excavator | Hr | 6.00 | 3997.47 | 23984.82 |

# RATE ANALYSIS (2082/083)

| | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Unskilled | md | 3.00 | 855.00 | 2565.00 | | | | | | | | | | |
| | | | | Sub total of A = | 3780.00 | | | | Sub total of B = | 0.00 | | | | Sub total of C = | 23984.82 |
| | | | | Sub total of A +B + C = | 27764.82 | | | | Contractor's overhead expenses 15% = | | 4164.72 | | | Unit Rate = | 31929.54 |
| | | | | | | | | | | | | | | Per M3 | 88.69 |

**Description of works:** Road way Excavation in ordinary rock as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer.(Mechanical Means)

Spec. cl. No: 905 — **Unit : 120 m3**

| Norms No. | Labour (A) | | | | | Material (B) | | | | | Equipment (C) | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount |
| 9.1 II B | Skilled | md | 1.00 | 1215.00 | 1215.00 | | | | | | Hydraulic Excavator | Hr | 6.00 | 3997.4700 | 23984.82 |
| | Unskilled | md | 3.00 | 855.00 | 2565.00 | | | | | | | | | | |
| | | | | Sub total of A = | 3780.00 | | | | Sub total of B = | 0.00 | | | | Sub total of C = | 23984.82 |
| | | | | Sub total of A +B + C = | 27764.82 | | | | Contractor's overhead expenses 15% = | | 4164.72 | | | Unit Rate = | 31929.54 |
| | | | | | | | | | | | | | | Rate per M3 | 266.08 |

**Description of works:** Roadway Excavation in hard rock with rock breakers, including breaking rock, lifts and lead for disposal as per Drawing and Technical Specifications Mechanical method, lead upto 30 m (Without Blasting)

Spec. cl. No: 905 — **Unit : 16 m3**

| Norms No. | Labour (A) | | | | | Material (B) | | | | | Equipment (C) | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount |
| 9.1 IV A | Skilled | md | 1.00 | 1215.00 | 1215.00 | | | | | | Hydraulic Excavator | Hr | 6.00 | 3997.4700 | 23984.82 |
| | Unskilled | md | 10.00 | 855.00 | 8550.00 | | | | | | | | | | |
| | | | | Sub total of A = | 9765.00 | | | | Sub total of B = | 0.00 | | | | Sub total of C = | 23984.82 |
| | | | | Sub total of A +B + C = | 33749.82 | | | | Contractor's overhead expenses 15% = | | 5062.47 | | | Unit Rate = | 38812.29 |
| | | | | | | | | | | | | | | Rate per m3 | 2425.77 |

**Description of works:** Roadway Excavation in hard rock with rock breakers, including breaking rock, lifts and lead for disposal as per Drawing and Technical Specifications Mechanical method, lead upto 30 m (Without Blasting)

Spec. cl. No: 905 — **Unit : 16 m3**

| Norms No. | Labour (A) | | | | | Material (B) | | | | | Equipment (C) | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount |
| 9.1 IV A | Skilled | md | 1.00 | 1215.00 | 1215.00 | | | | | | Hydraulic Excavator | Hr | 6.00 | 3997.4700 | 23984.82 |
| | Unskilled | md | 10.00 | 855.00 | 8550.00 | | | | | | | | | | |
| | | | | Sub total of A = | 9765.00 | | | | Sub total of B = | 0.00 | | | | Sub total of C = | 23984.82 |
| | | | | Sub total of A +B + C = | 33749.82 | | | | Contractor's overhead expenses 15% = | | 5062.47 | | | Unit Rate = | 38812.29 |
| | | | | | | | | | | | | | | Rate per m3 | 2425.77 |

**Description of works:** Roadway Excavation in hard rock with mechanical drilling, including blasting and breaking, and disposal of cut road within the lift and lead as per Drawings and instruction of engineer (With Blasting)

Spec. cl. No: 905 — **Unit : 90 m3**

| Norms No. | Labour (A) | | | | | Material (B) | | | | | Equipment (C) | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount |
| 9.1 III A | Skilled | md | 1.00 | 1215.00 | 1215.00 | Gelatin | Kg | 32 | 217.98 | 6975.36 | Dozer | Hr | 6.00 | 3997.47 | 23984.82 |
| | Unskilled | md | 20.00 | 855.00 | 17100.00 | Electric Detonators | nos | 126 | 152.79 | 19251.54 | Jack Hammer/Rock Drill | Hr | 30.00 | 611.13 | 18333.90 |
| | Driller | md | 3.00 | 1215.00 | 3645.00 | Fuse Wire | meter | 180 | 7.02834 | 1265.1012 | Air Compressor | Hr | 12.00 | 1727.47 | 20729.64 |
| | Blaster | md | 1.00 | 1215.00 | 1215.00 | | | | | | | | | | |
| | | | | Sub total of A = | 23175.00 | | | | Sub total of B = | 26226.90 | | | | Sub total of C = | 63048.36 |

# RATE ANALYSIS (2082/083)

| | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | Sub total of A +B + C = | 112450.26 | | | | | Contractor's overhead expenses 15% = | 16867.54 | | | | Unit Rate = | 129317.80 |
| | | | | | | | | | | | | | | | Rate per m3 | 1436.86 |
| Description of works: | | Removal of Unserviceable soil including excavation, loading and disposal up to 1000 m lead | | | | | | | | | | | | | | Unit : 360 m3 |
| Spec. cl. No: 905 | | | | | | | | | | | | | | | | |
| Norms No. | Labour (A) | | | | | Material (B) | | | | | Equipment (C) | | | | | |
| | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount | |
| 9.2 | Skilled | md | 1.00 | 1215.00 | 1215.00 | | | | | | Excavator | Hr | 6.00 | 3997.47 | 23984.82 | |
| | Unskilled | md | 4.00 | 855.00 | 3420.00 | | | | | | Tripper | Hr | 18.00 | 1729.71 | 31134.78 | |
| | | | | Sub total of A = | 4635.00 | | | | Sub total of B = | 0.00 | | | | | Sub total of C = | 55119.60 |
| | | | | Sub total of A +B + C = | 59754.60 | | | | | Contractor's overhead expenses 15% = | 8963.19 | | | | Unit Rate = | 68717.79 |
| | | | | | | | | | | | | | | | Rate per m3 | 190.88 |

## Excavation for Structures Foundation

| | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Description of works: | | Earth work in excavation of foundation of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications. Ordinary soil Mechanical Means ( Depth upto 3 M) | | | | | | | | | | | | | | Unit : 240 m3 |
| Spec. cl. No: 907 | | | | | | | | | | | | | | | | |
| Norms No. | Labour (A) | | | | | Material (B) | | | | | Equipment (C) | | | | | |
| | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount | |
| 9.4 B.i | Skilled | md | 1.00 | 1215.00 | 1215.00 | | | | | | Excavator | hr | 6.00 | 3997.470 | 23984.82 | |
| | Unskilled | md | 3.00 | 855.00 | 2565.00 | | | | | | | | | | | |
| | | | | Sub total of A = | 3780.00 | | | | Sub total of B = | 0.00 | | | | | Sub total of C = | 23984.82 |
| | | | | Sub total of A +B + C = | 27764.82 | | | | | Contractor's overhead expenses 15% = | 4164.72 | | | | Unit Rate = | 31929.54 |
| | | | | | | | | | | | | | | | Rate per m3 | 133.04 |
| Description of works: | | Earth work in excavation of foundation of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications. Ordinary soil Mechanical Means ( Depth upto 3 - 6 M) | | | | | | | | | | | | | | Unit : 210 m3 |
| Spec. cl. No: 907 | | | | | | | | | | | | | | | | |
| Norms No. | Labour (A) | | | | | Material (B) | | | | | Equipment (C) | | | | | |
| | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount | Type | Unit | Qty. | Rate | Amount | |
| 9.4 B.ii | Skilled | md | 1.00 | 1215.00 | 1215.00 | | | | | | Excavator | hr | 6.00 | 3997.47 | 23984.82 | |
| | Unskilled | md | 3.00 | 855.00 | 2565.00 | | | | | | | | | | | |
| | | | | Sub total of A = | 3780.00 | | | | Sub total of B = | 0.00 | | | | | Sub total of C = | 23984.82 |
| | | | | Cost of Dewatering @ 7.5% of A+C | 2082.36 | | | | | | | | | | | |
| | | | | Sub total of A +B + C = | 29847.18 | | | | | Contractor's overhead expenses 15% = | 4477.08 | | | | Unit Rate = | 34324.26 |
| | | | | | | | | | | | | | | | Rate per m3 | 163.45 |