RATE ANALYSIS (2082/083)

Description of works:	Earth work in excavation of foundation of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications.	Unit : 180 m3
Spec. cl. No: 907	Ordinary soil Mechanical Means (Depth Above 6 M)	

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
9.4 B.iii	Skilled	md	2.00	1215.00	2430.00						Excavator	hr	6.00	3997.47	23984.82
	Unskilled	md	4.00	855.00	3420.00										
				Sub total of A =	5850.00				Sub total of B =	0.00				Sub total of C =	23984.82
				Cost of Dewatering @ 10% of A+C	2983.48										
				Sub total of A +B + C =	32818.30				Contractor's overhead expenses 15% =		4922.75			Unit Rate =	37741.05
														Rate per m3	209.67

Description of works:	Earth work in excavation of foundation of structures, including construction of shoring andbracing, removal of stumps and other deleteriousmatter and backfilling with approved Material asper Drawing and Technical Specifications.	Unit : 90 m3
Spec. cl. No: 907	Ordinary Rock Mechanical Means	

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
9.4 II b	Skilled	md	1.00	1215.00	1215.00						Excavator	hr	6.00	3997.47	23984.82
	Unskilled	md	3.00	855.00	2565.00										
				Sub total of A =	3780.00				Sub total of B =	0.00				Sub total of C =	23984.82
				Cost of Dewatering @ 10% of A+C	2776.48										
				Sub total of A +B + C =	30541.30				Contractor's overhead expenses 15% =		4581.20			Unit Rate =	35122.50
														Rate per m3	390.25

Description of works:	Earth work in excavation of foundation of structures, including construction of shoring and bracing, removal of stumps and other deleteriousmatter and backfilling with approved Material as per Drawing and Technical Specifications.	Unit : 10 m3
Spec. cl. No: 907	Hard Rock	

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
9.4 .iv.a	Skilled	md	1.00	1215.00	1215.00						Air Compressor	hr	3.00	1727.47	5182.41
	UnSkilled	md	10.00	855.00	8550.00						Jack Hammer/Rock Drill	hr	3.00	611.13	1833.39
				Sub total of A =	9765.00				Sub total of B =	0.00				Sub total of C =	7015.80
				Cost of Dewatering @ 10% of A+C	1678.08										
				Sub total of A +B + C =	18458.88				Contractor's overhead expenses 15% =		2768.83			Unit Rate =	21227.71
														Rate per m3	2122.77

RATE ANALYSIS (2082/083)

Description of works:	Preparation and Surface Treatment of formation by removing mud and slurry, watering to the extent needed to maintain desire moisture content compacting all complete as per drawing and technical specification	Unit : 3500 Sqm
Spec. cl. No: 909, 910		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
9.7	Skilled	md	1.00	1215.00	1215.00	Water	L	18000	0.1925	3465	Vibratory Roller	hr	6.00	2626.11	15756.66
	Unskilled	md	10.00	855.00	8550.00										
				Sub total of A =	9765.00				Sub total of B =	3465.00				Sub total of C =	15756.66
				Sub total of A +B + C =	28986.66				Contractor's overhead expenses 15% =		4348.00			Unit Rate =	33334.66
														Rate per m3	9.52

Description of works:	Construction of Embankment with Material obtained from borrow pits Providing, Laying, Spreading and Compacting embankment with borrow material as per Drawing and Technical Specification	Unit : 300 m3
Spec. cl. No: 909, 910		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
9.8	Skilled	md	1.00	1215.00	1215.00	Water	L	72000	0.1925	13860	Excavator	hr	6.00	3997.47	23984.82
	Unskilled	md	4.00	855.00	3420.00	Borrow Pit Material	Cum	360	50.93	18334.8	Tractor-Rotavator	hr	12.00	1283.38	15400.56
											Dozer	hr	3.00	6553.96	19661.88
											Motor Grader	hr	3.00	3957.50	11872.50
											Vibratory Roller	hr	6.00	2626.11	15756.66
				Sub total of A =	4635.00				Sub total of B =	32194.80				Sub total of C =	86676.42
				Sub total of A +B + C =	123506.22				Contractor's overhead expenses 15% =		18525.93			Unit Rate =	142032.15
														Rate per m3	473.44

Description of works:	Construction of Embankment with Material deposited from roadway cutting Providing, Laying, Spreading and Compacting embankment withdeposited material as per Drawing and Technical Specification	Unit : 300 m3
Spec. cl. No: 909, 910		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
9.9 B	Skilled	md	1.00	1215.00	1215.00	Water	L	72000	0.1925	13860	Dozer	hr	6.00	6553.96	39323.76
	Unskilled	md	10.00	855.00	8550.00						Motor Grader	hr	6.00	3957.50	23745.00
											Vibratory Roller	hr	6.00	2626.11	15756.66
				Sub total of A =	9765.00				Sub total of B =	13860.00				Sub total of C =	78825.42
				Sub total of A +B + C =	102450.42				Contractor's overhead expenses 15% =		15367.56			Unit Rate =	117817.98
														Rate per m3	392.73

RATE ANALYSIS (2082/083)

Description of works:	Providing Granular Material and back filling behind abutment, wing wall and return wall complete as per Drawing and Techinical Specifications.	Unit : 10 m3
Spec. cl. No: 908		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
9.11 A	Skilled	md	0.20	1215.00	243.00	Granular Material	Cum	11	592.00	6512	Plate Compactor/Power rammer	hr	2.50	1262.16	3155.40
	Unskilled	md	5.00	855.00	4275.00	Water	L	1000	0.1925	192.5					
				Sub total of A =	4518.00				Sub total of B =	6704.50				Sub total of C =	3155.40
				Sub total of A +B + C =	14377.90					Contractor's overhead expenses 15% =	2156.69			Unit Rate =	16534.59
														Rate per m3	1653.46

Description of works:	Providing Sandy Material and back filling behind abutment, wing wall and return wall complete as per Drawing and Techinical Specifications.	Unit : 10 m3
Spec. cl. No: 908		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
9.11 B	Skilled	md	0.20	1215.00	243.00	Sand	Cum	12	2329	27948	Plate Compactor/Power rammer	hr	2.50	1262.16	3155.40
	Unskilled	md	5.00	855.00	4275.00	Water	L	1000	0.1925	192.5					
				Sub total of A =	4518.00				Sub total of B =	28140.50				Sub total of C =	3155.40
				Sub total of A +B + C =	35813.90					Contractor's overhead expenses 15% =	5372.09			Unit Rate =	41185.99
														Rate per m3	4118.60

Description of works:	Providing Locally available Material including compaction by tamping rod (with watering) and back filling behind abutment, wing wall and return wall complete as per Drawing and Techinical Specifications.	Unit : 10 m3
Spec. cl. No: 908		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
9.11 C	Skilled	md	0.20	1215.00	243.00	Compensation for Locally available Material	Cum	12	50.93	611.16	Tamping	3% of Labour Cost		135.54	135.54
	Unskilled	md	5.00	855.00	4275.00	Water	L	1000	0.1925	192.5					
				Sub total of A =	4518.00				Sub total of B =	803.66				Sub total of C =	135.54
				Sub total of A +B + C =	5457.20					Contractor's overhead expenses 15% =	818.58			Unit Rate =	6275.78
														Rate per m3	627.58

RATE ANALYSIS (2082/083)

Description of works:	Providing and Laying of Filter media with grannular Material/stone crushed aggregates to a thickness of not less than 600 mm with smaller size towards the soil and bigger size towards the wall and provided over the entire surface behind abutement, wing wall and return wall to the full height compacted to a firm condition complete as per drawing and Technical specification.	Unit : 10 m3
Spec. cl. No: 909, 910		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
9.12	Skilled	md	1.00	1215.00	1215.00	Filter media	cum	12	2218.00	26616					0.00
	Unskilled	md	10.00	855.00	8550.00	Water	L	1000	0.1925	192.5					0.00
															0.00
				Sub total of A =	9765.00				Sub total of B =	26808.50				Sub total of C =	0.00
				Sub total of A +B + C =	36573.50				Contractor's overhead expenses 15% =		5486.03			Unit Rate =	42059.53
														Rate per m3	4205.95

Description of works:	Scarifying the existing road surface to a depth of 50 mm and disposal of scarified Material with all lifts and leads as per Drawing and Technical Specifications. By Manual Means	Unit : 600 m^2
Spec. cl. No: 1003		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
10.1 A	Skilled	md	1.00	1215.00	1215.00						Tractor-trolley/ Truck	hr	6.00	1316.38	7898.28
	Unskilled	md	15.00	855.00	12825.00										
				Sub total of A =	14040.00				Sub total of B =	0.00				Sub total of C =	7898.28
				Sub total of A +B + C =	21938.28				Contractor's overhead expenses 15% =		3290.74			Unit Rate =	25229.02
														Rate Per Sq M =	42.05

Description of works:	Scarifying the existing road surface to a depth of 50 mm and disposal of scarified Material with all lifts and leads as per Drawing and Technical Specifications. By Mechanical Means lead up to 30 m	Unit : 600 m^2
Spec. cl. No: 1003		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
10.2 A	Skilled	md	1.00	1215.00	1215.00						Tractor with Ripper	hr	6.00	1316.38	7898.28
	Unskilled	md	6.00	855.00	5130.00										
				Sub total of A =	6345.00				Sub total of B =	0.00				Sub total of C =	7898.28
				Sub total of A +B + C =	14243.28				Contractor's overhead expenses 15% =		2136.49			Unit Rate =	16379.77
														Rate Per Sq M =	27.30

Description of works:	Scarifying the existing granular road surface to a depth of 50 mm and disposal of scarified Material with all lifts and leads within Right of way as per Drawing and Technical Specifications by Manual means lead up to 30 m	Unit : 600 m^2
Spec. cl. No: 1003		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
10.1 B	Skilled	md	1.00	1215.00	1215.00										
	Unskilled	md	12.00	855.00	10260.00										
				Sub total of A =	11475.00				Sub total of B =	0.00				Sub total of C =	0.00
				Sub total of A +B + C =	11475.00				Contractor's overhead expenses 15% =		1721.25			Unit Rate =	13196.25
														Rate Per Sq M =	21.99

RATE ANALYSIS (2082/083)

Description of works:	Scarifying the existing granular road surface to a depth of 50 mm and disposal of scarified Material with all lifts and leads within Right of way as per Drawing and Technical Specifications by Mechanical means	Unit : 3000 m^2
Spec. cl. No: 1003		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
10.2 B	Skilled	md	1.00	1215.00	1215.00						Tractor with Ripper	hr	6.00	1316.38	7898.28
	Unskilled	md	6.00	855.00	5130.00						Loader	hr	6.00	3265.15	19590.90
											Tipper	hr	6.00	1729.71	10378.26
				Sub total of A =	6345.00				Sub total of B =	0.00				Sub total of C =	37867.44
				Sub total of A +B + C =	44212.44				Contractor's overhead expenses 15% =		6631.87			Unit Rate =	50844.31
														Rate Per Sq M =	16.95

Description of works:	Compacting original ground supporting sub-grade Loosening of the ground upto a level of 500 mm below the sub-grade level, watered, graded and compacted in layers as per Drawing and Technical Specifications.	Unit : 600 m^3
Spec. cl. No: 1003,1005		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
10.4i	Skilled	md	1.00	1215.00	1215.00	Water	lit	24000.00	0.19	4620.00	Grader	hr	6.00	3957.50	23745.00
	Unskilled	md	5.00	855.00	4275.00						Vibratory road Roller	hr	12.00	2626.11	31513.32
											Tractor with ripper	hr	12.00	1316.380	15796.56
				Sub total of A =	5490.00				Sub total of B =	4620.00				Sub total of C =	71054.88
				Sub total of A +B + C =	81164.88				Contractor's overhead expenses 15% =		12174.73			Unit Rate =	93339.61
														Rate Per m3	155.57
														avg 20 cm	31.11

Description of works:	Compacting original ground supporting embankment Loosening, leveling and Compacting original ground supporting embankment to facilitate placement of first layer of embankment, scarified to a depth of 150 mm, mixed with water at OMC and then compacted by rolling so as to achieve dry density as per Drawing and Technical Specifications.	Unit : 600 m^3
Spec. cl. No: 1003,1005		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
10.4ii	Skilled	md	1.00	1215.00	1215.00	Water	lit	24000.00	0.19	4620.00	Grader	hr			0.00
	Unskilled	md	4.00	855.00	3420.00						Vibratory road Roller	hr	12.00	2626.11	31513.32
											Tractor with ripper	hr	6.00	1316.380	7898.28
				Sub total of A =	4635.00				Sub total of B =	4620.00				Sub total of C =	39411.60
				Sub total of A +B + C =	48666.60				Contractor's overhead expenses 15% =		7299.99			Unit Rate =	55966.59
														Rate Per m3	93.28
															13.9916475

Description of works:	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications. By Mechanical Means	Unit : 300 m^3
Spec. cl. No: 1201		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
12.1A	Skilled	md	2.00	1215.00	2430.00	Subbase material S1 type or S2 type	cu.m.	384.0	1184.00	454656.00	Grader	hr	6.00	3957.50	23745.00
	Unskilled	md	12.00	855.00	10260.00	Cost of Water	lit	18000.0	0.19	3465.00	Vibrator Roller	hr	12.00	2626.11	31513.32
											Tractor/Loader	hr	12.00	3265.15	39181.80
				Sub total of A =	12690.00				Sub total of B =	458121.00				Sub total of C =	94440.12
				Sub total of A +B + C =	565251.12				Contractor's overhead expenses 15% =		84787.67			Unit Rate =	650038.79
														Unit Rate Per M3=	2166.80