RATE ANALYSIS (2082/083)

					Sub total of A =	1282.50				Sub total of B =	2661.60			Sub total of C =	0.00
					Sub total of A +B + C =	3944.10				Contractor's overhead expenses 15% =	591.62			Unit Rate :	4535.72
														Rate Per M3	4535.72
Description of works:															
Spec. cl. No: 1401															Unit : 400 meter

Providing and Lyaing of M20 Precast Cement Concrete Kerb 35 cm * 20 cm * 30 cm (H*B*L) with 12 mm thick 1:3 cement sand mortar bedding and joints including foundation excavation levelling but excluding foundation concrete for foundation or sand gravel material, all complete as per Drawing and Technical Specifications.

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
14.1	Skilled	md	3.00	1215.00	3645.00	Precast / Cast in situ concrete block of /20 Concrete (0.38m * 0.20m *0.25m (H*B*L))	nos.	1600.000	381.98	611168.00	Kerb Casting Machine	Hr.	6.00		0.00
	Unskilled	md	16.00	855.00	13680.00	Coarse Sand 30%	m^3	1.200	2329.00	2794.80	Concrete Mixer	Hr.	12.00		0.00
						Cement	tonne	0.520	13500.00	7020.00					
						water	lit	200.00	0.19	38.50					
					Sub total of A =	17325.00				Sub total of B =	621021.30			Sub total of C =	0.00
					Sub total of A +B + C =	638346.30				Contractor's overhead expenses 15% =	95751.95			Unit Rate :	734098.25
	Remarks: Foundation concrete or sand gravel to be measured and paid separately as required from respective clause of specification.													Rate Per m=	1835.25
										15000	0.02				

Description of works:															
Spec. cl. No: 1401															Unit : 10 Sqm

Providing and Laying of precast / cast in situ 50 mm thick cement concrete slab footpath on 12mm thick 1:3 cement sand mortar over the prepared base, all complete as per Drawing and Technical Specifications.

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
14.2 A	Skilled	md	1.50	1215.00	1822.50	Precast / cast in situ concrete block of M20/20 (50 mm CC Blocks)	sqm	11.000	1452.60	15978.60					
	Unskilled	md	4.00	855.00	3420.00	Coarse Sand	m^3	0.130	2329.00	302.77					
						Cement	tonne	0.070	13500.00	945.00					
						water	lit	200.00	0.19	38.50					
					Sub total of A =	5242.50				Sub total of B =	17264.87			Sub total of C =	0.00
					Sub total of A +B + C =	22507.37				Contractor's overhead expenses 15% =	3376.11			Unit Rate :	25883.48
	Remarks: Foundation concrete or sand gravel to be measured and paid separately as required from respective clause of specification.													Rate Per m2=	2588.35

Description of works:															
Spec. cl. No: 1401															Unit : 10 Sqm

Providing and laying 50 mm thick Natural stone slab footpath on 12 mm thick 1:3 cement sand mortar over the prepared base, all complete as per specification.

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
14.2 B	Skilled	md	2.00	1215.00	2430.00	50 mm thick natural stone slab	sqm	11.000	1135.74	12493.14					
	Unskilled	md	3.00	855.00	2565.00	Sand	m^3	0.130	2329.00	302.77					
						Cement	tonne	0.070	13500.00	945.00					
						water	lit	200.00	0.19	38.50					
					Sub total of A =	4995.00				Sub total of B =	13779.41			Sub total of C =	0.00
					Sub total of A +B + C =	18774.41				Contractor's overhead expenses 15% =	2816.16			Unit Rate :	21590.57
														Rate Per m2=	2159.06

RATE ANALYSIS (2082/083)

Description of works:	Providing and laying brick on edge over 60 mm thick sand bed in footpath including excavation sand bedding all complete as per Drawing and Technical Specifications.														Unit : 10 Sqm
Spec. cl. No: 1403															
Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
14.5 A	Skilled	md	1.00	1215.00	1215.00	Bricks	nos.	750.000	17.20	12900.00					
	Unskilled	md	3.00	855.00	2565.00	Coarse Sand	m^3	0.700	2329.00	1630.30					
				Sub total of A =	3780.00				Sub total of B =	14530.30				Sub total of C =	0.00
				Sub total of A +B + C =	18310.30				Contractor's overhead expenses 15% =		2746.55			Unit Rate :	21056.85
														Rate Per m2=	2105.68

Description of works:	Providing and laying flat brick over 60 mm thick sand bed in footpath including excavation sand bedding all complete as per Specification.														Unit : 20 Sqm
Spec. cl. No: 1403															
Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
14.5 B	Skilled	md	1.50	1215.00	1822.50	Bricks	nos.	750.000	17.20	12900.00					
	Unskilled	md	4.00	855.00	3420.00	Sand	m^3	1.400	2329.00	3260.60					
				Sub total of A =	5242.50				Sub total of B =	16160.60				Sub total of C =	0.00
				Sub total of A +B + C =	21403.10				Contractor's overhead expenses 15% =		3210.47			Unit Rate :	24613.57
														Rate Per m2=	1230.68

Description of works:	Providing and laying Random rubble stone masonry in cement mortar [cement(1) : sand(4)] in Foundation complete as per drawing and technical specification. Manual Mixed Mortar														Unit : 5 m3
Spec. cl. No: 2602,2603,2607															
Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
26.3.b	Skilled	md	7.00	1215.00	8505.00	Cement	t	0.620	13500.00	8370.00	Concrete mixer or other tools 5 % of L C		0.05	of L.C.	1023.75
	Unskilled	md	14.00	855.00	11970.00	Sand	m^3	1.740	2329.00	4052.46					
						Stone	m^3	5.750	2218.00	12753.50					
						water	lit	1000.00	0.19	192.50					
				Sub total of A =	20475.00				Sub total of B =	25368.46				Sub total of C =	1023.75
				Sub total of A +B + C =	46867.21				Contractor's overhead expenses 15% =		7030.08			Rate per 5 m3 =	53897.29
														Rate Per m3=	10779.46

RATE ANALYSIS (2082/083)

Description of works:	Providing and laying Random rubble stone masonry in cement mortar [cement(1) : sand(4)] in Foundation complete as per drawing and technical specification. Machine Mixed Mortar	Unit : 5 m3
Spec. cl. No: 2602,2603,2607		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
26.3.b	Skilled	md	7.00	1215.00	8505.00	Cement	t	0.620	13500.00	8370.00	Concrete mixer	hr	0.75	826.26	619.70
	Unskilled	md	9.00	855.00	7695.00	Sand	m^3	1.740	2329.00	4052.46					
						Stone	m^3	5.750	2218.00	12753.50					
						water	lit	1000.00	0.19	192.50					
				Sub total of A =	16200.00				Sub total of B =	25368.46				Sub total of C =	619.70
				Sub total of A +B + C =	42188.16				Contractor's overhead expenses 15% =		6328.22			Rate per 5 m3 =	**48516.38**
														Rate Per m3=	**9703.28**

Description of works:	Providing and laying Random rubble stone masonry in cement mortar [cement(1) : sand(6)] in Foundation complete as per drawing and technical specification.	Unit : 5 m3
Spec. cl. No: 2602,2603,2607		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
26.3.C	Skilled	md	7.00	1215.00	8505.00	Cement	t	0.450	13500.00	6075.00					
	Unskilled	md	14.00	855.00	11970.00	Sand	m^3	2.080	2329.00	4844.32					
						Stone	m^3	5.750	2218.00	12753.50					
						water	lit	1000.00	0.19	192.50					
				Sub total of A =	20475.00				Sub total of B =	23865.32				Sub total of C =	0.00
				Sub total of A +B + C =	44340.32				Contractor's overhead expenses 15% =		6651.05			Rate per 5 m3 =	**50991.37**
														Rate Per m3=	**10198.27**

Description of works:	Providing and laying Random rubble stone masonry in cement mortar [cement(1) : sand(4)] in Structure complete as per drawing and technical specification	Unit : 5 m3
Spec. cl. No: 2600, 2607		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
26.5 A	Skilled	md	7.00	1215.00	8505.00	Cement	t	0.660	13500.00	8910.00	Scaffolding 5 % of L C and MC		0.05	of L.C.	2588.48
	Unskilled	md	20.00	855.00	17100.00	Sand	m^3	1.850	2329.00	4308.65					
						Stone	m^3	5.750	2218.00	12753.50					
						water	lit	1000.00	0.1925	192.50					
				Sub total of A =	25605.00				Sub total of B =	26164.65				Sub total of C =	2588.48
				Sub total of A +B + C =	54358.13				Contractor's overhead expenses 15% =		8153.72			Rate per 5 m3 =	**62511.85**
														Rate Per m3=	**12502.37**

RATE ANALYSIS (2082/083)

Description of works:	Providing and laying Random rubble stone masonry in cement mortar [cement(1) : sand(6)] in Structure complete as per drawing and technical specification	Unit : 5 m3
Spec. cl. No: 2600, 2607		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
26.6 A	Skilled	md	7.00	1215.00	8505.00	Cement	t	0.480	13500.00	6480.00	Scaffolding 5 % of L C and M C		0.05	of L.C.	2482.12
	Unskilled	md	20.00	855.00	17100.00	Sand	m^3	1.980	2329.00	4611.42					
						Stone	m^3	5.750	2218.00	12753.50					
						water	lit	1000.00	0.19	192.50					
				Sub total of A =	25605.00				Sub total of B =	24037.42				Sub total of C =	2482.12
				Sub total of A +B + C =	52124.54				Contractor's overhead expenses 15% =		7818.68			0	59943.22
														Rate per m3	11988.64

Description of works:	Providing , Preparing and Installing form work including necessary supports and removing after completion for foundation and footings (a) using timber (soft wood) - Class F1 finish.	Unit : 10 m2
Spec. cl. No: 1804,1805		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
18.1	Skilled	md	1.50	1215.00	1822.50	Planks 38mm thick.	m^3	0.42	5557.79	2334.27					
	Unskilled	md	2.00	855.00	1710.00	struts, ballies, etc.	m^3	0.18	3705.19	666.93					
						Nails,spikes,etc.	kg	1.00	122.90	122.90					
				Sub total of A =	3532.50				Sub total of B =	3124.10				Sub total of C =	0.00
				Sub total of A +B + C =	6656.60				Contractor's overhead expenses 15% =		998.49			Rate (10 m2) =	7655.09
														Unit Rate (1 m2) =	765.51

Description of works:	Providing , Preparing and Installing form work including necessary supports and removing after completion ---For Vertical plain surface [class F2 finish] height upto 3 m	Unit : 10 m2
Spec. cl. No: 1804,1805		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
18.2.a.i	Skilled	md	2.20	1215.00	2673.00	Struts ballies	m3	0.40	3705.19	1482.07					
	Unskilled	md	2.20	855.00	1881.00	Nails,spikes,etc.	kg	2.50	122.90	307.25					
						Plywood 9mm thick	m2	11.00	100.69	1107.53					
				Sub total of A =	4554.00				Sub total of B =	2896.85				Sub total of C =	0.00
				Sub total of A +B + C =	7450.85				Contractor's overhead expenses 15% =		1117.63			Unit Rate :	8568.48
														Unit Rate (1 m2) =	856.85

RATE ANALYSIS (2082/083)

Description of works:	Providing , Preparing and Installing form work including necessary supports and removing after completion ---For Vertical plain surface [class F2 finish] height 3 m upto 6m.	Unit : 10 m2
Spec. cl. No: 1804,1805		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
18.2.a.ii	Skilled	md	2.60	1215.00	3159.00	Struts ballies	m3	0.50	3705.19	1852.59					
	Unskilled	md	2.80	855.00	2394.00	Nails,spikes,etc.	kg	3.50	122.90	430.15					
						Plywood 9mm thick	m2	11.00	100.69	1107.53					
				Sub total of A =	5553.00				Sub total of B =	3390.27				Sub total of C =	0.00
				Sub total of A +B + C =	8943.27				Contractor's overhead expenses 15% =		1341.49			Unit Rate :	10284.76
														Unit Rate (1 m2) =	1028.48

Description of works:	Providing , Preparing and Installing form work including necessary supports and removing after completion ---For Vertical plain surface [class F2 finish] height 6.0 m upto 9.0 m	Unit : 10 m2
Spec. cl. No: 1804,1805		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
18.2.a.iii	Skilled	md	3.20	1215.00	3888.00	Struts ballies	m3	0.60	3705.19	2223.11					
	Unskilled	md	4.00	855.00	3420.00	Nails,spikes,etc.	kg	4.50	122.90	553.05					
						Plywood 9mm thick	m2	11.00	100.69	1107.53					
				Sub total of A =	7308.00				Sub total of B =	3883.69				Sub total of C =	0.00
				Sub total of A +B + C =	11191.69				Contractor's overhead expenses 15% =		1678.75			Unit Rate :	12870.44
														Unit Rate (1 m2) =	1287.04

Description of works:	Providing , Preparing and Installing form work including necessary supports and removing after completion ---For Vertical curved surface [class F2 finish] height upto 3.0 m.	Unit : 10 m2
Spec. cl. No: 1804,1805		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
18.3.a.i	Skilled	md	3.00	1215.00	3645.00	Struts ballies	m3	0.60	3705.19	2223.11					
	Unskilled	md	3.00	855.00	2565.00	Nails,spikes,etc.	kg	4.00	122.90	491.60					
						Plywood 9mm thick	m2	11.00	100.69	1107.53					
				Sub total of A =	6210.00				Sub total of B =	3822.24				Sub total of C =	0.00
				Sub total of A +B + C =	10032.24				Contractor's overhead expenses 15% =		1504.84			Unit Rate :	11537.08
														Unit Rate (1 m2) =	1153.71

Description of works:	Providing , Preparing and Installing form work including necessary supports and removing after completion ---For Vertical curved surface [class F2 finish] height 3.0 m upto 6.0 m.	Unit : 10 m2
Spec. cl. No: 1804,1805		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
18.3.a.ii	Skilled	md	3.50	1215.00	4252.50	Struts ballies	m3	0.72	3705.19	2667.73					
	Unskilled	md	3.80	855.00	3249.00	Nails,spikes,etc.	kg	5.00	122.90	614.50					
						Plywood 9mm thick	m2	11.00	100.69	1107.53					
				Sub total of A =	7501.50				Sub total of B =	4389.76				Sub total of C =	0.00
				Sub total of A +B + C =	11891.26				Contractor's overhead expenses 15% =		1783.69			Unit Rate :	13674.95
														Unit Rate (1 m2) =	1367.49