RATE ANALYSIS (2082/083)

Description of works:	Providing , Preparing and Installing form work including necessary supports and removing after completion ---For Vertical curved surface [class F2 finish] height 6.0 m upto 9.0 m.	Unit : 10 m2
Spec. cl. No: 1804,1805		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
18.3.a.iii	Skilled	md	4.30	1215.00	5224.50	Struts ballies	m3	0.90	3705.19	3334.67					
	Unskilled	md	5.40	855.00	4617.00	Nails,spikes,etc.	kg	6.00	122.90	737.40					
						Plywood 9mm thick	m2	11.00	100.69	1107.53					
				Sub total of A =	9841.50				Sub total of B =	5179.60				Sub total of C =	0.00
				Sub total of A +B + C =	15021.10				Contractor's overhead expenses 15% =		2253.17			Unit Rate :	17274.27
														Unit Rate (1 m2) =	1727.43

Description of works:	Providing , Preparing and Installing form work including necessary supports and removing after completion ---For slab structure [class F2 finish] using timber planks. (Falsework not included)	Unit : 10 m2
Spec. cl. No: 1804,1805		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
18.6.a	Skilled	md	1.80	1215.00	2187.00	Plank 38 mm	m^3	0.540	7410.39	4001.60					
	Unskilled	md	2.50	855.00	2137.50	Nails, spikes,etc.	kg	2.500	122.90	307.25					
				Sub total of A =	4324.50				Sub total of B =	4308.85				Sub total of C =	0.00
				Sub total of A +B + C =	8633.35				Contractor's overhead expenses 15% =		1295.00			Unit Rate =	9928.35
														Rate (1 m2)	992.84

Description of works:	Providing , Preparing and Installing form work including necessary supports and removing after completion ---For slab and beam structure [class F2 finish] using timber planks. (Falsework not included)	Unit : 10 m2
Spec. cl. No: 1804,1805		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
18.7.a	Skilled	md	3.00	1215.00	3645.00	Timber	m^3	0.820	7410.39	6076.51					
	Unskilled	md	3.00	855.00	2565.00	Nails, spikes,etc.	kg	4.000	122.90	491.60					
				Sub total of A =	6210.00				Sub total of B =	6568.11				Sub total of C =	0.00
				Sub total of A +B + C =	12778.11				Contractor's overhead expenses 15% =		1916.72			Unit Rate =	14694.83
														Rate (1 m2)	1469.48

Description of works:	Providing, and assembling in position falsework for the construction of RCC superstructure and removal after completion including necessary design and drawings as per specification. A) For Slabs and Box culverts , using timber for height 2m ~ 4m	Unit : 10 m2
Spec. cl. No: 1804,1805		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
18.10.a.ii	Skilled	md	16.00	1215.00	19440.00	Timber	m^3	1.400	5557.79	7780.90					
	Unskilled	md	18.00	855.00	15390.00	Nails, spikes,etc.	kg	4.000	122.90	491.60					
				Sub total of A =	34830.00				Sub total of B =	8272.50				Sub total of C =	0.00
				Sub total of A +B + C =	43102.50				Contractor's overhead expenses 15% =		6465.38			Unit Rate =	49567.88
														Rate (1 m2)	4956.79

RATE ANALYSIS (2082/083)

Description of works:	Providing, and assembling in position falsework for the construction of RCC superstructure and removal after completion including necessary design and drawings as per specification.	Unit : 10 m2
Spec. cl. No: 1804,1805	A) For RCC beam bridges , using timber for height 3m ~ 6m	

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
18.11.a.ii	Skilled	md	28.00	1215.00	34020.00	Timber	m^3	4.000	5557.79	22231.15					
	Unskilled	md	32.00	855.00	27360.00	Nails, spikes,etc.	kg	12.000	122.90	1474.80					
				Sub total of A =	61380.00				Sub total of B =	23705.95				Sub total of C =	0.00
				Sub total of A +B + C =	85085.95				Contractor's overhead expenses 15% =		12762.89			Unit Rate =	97848.84
														Rate (1 m2)	9784.88

Description of works:	Providing and placing machine mixed M10(or 1:3:6 for nominal mix) cement concrete for the foundation and footing etc. including compaction, curing, testing and lead 30m. etc. all complete as per specification and drawing.	Unit : 15 m3
Spec. cl. No: 2000		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
20.1	Skilled	md	2.00	1215.00	2430.00	cement	mt	3.450	13500.00	46575.00	mixer (0.28/ 0.20 m^3)	hr	6.00	826.26	4957.56
	Unskilled	md	22.00	855.00	18810.00	aggregate 20-40mm	m^3	13.500	1990.00	26865.00	Generator	hr	6.00	1173.44	7040.64
						coarse sand	m^3	6.750	2329.00	15720.75					
						water	lit	2000.000	0.19	385.00					
				Sub total of A =	21240.00				Sub total of B =	89545.75				Sub total of C =	11998.20
				Sub total of A +B + C =	122783.95				Contractor's overhead expenses 15% =		18417.59			Total Rate =	141201.54
														Rate per m3	9413.44

Description of works:	Providing and placing M10 (or 1:3:6 for nominal mix) cement concrete for the foundation and footing etc. including compaction, curing, testing and lead 30m. etc. all complete as per specification and drawing. Manual Method	Unit : 15 m3
Spec. cl. No: 2000		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
20.1	Skilled	md	3.00	1215.00	3645.00	cement	mt	3.450	13500.00	46575.00					
	Unskilled	md	33.00	855.00	28215.00	aggregate 20-40mm	m^3	13.500	1990.00	26865.00					
						coarse sand	m^3	6.750	2329.00	15720.75					
						water	lit	2000.000	0.19	385.00					
				Sub total of A =	31860.00				Sub total of B =	89545.75				Sub total of C =	0.00
				Sub total of A +B + C =	121405.75				Contractor's overhead expenses 15% =		18210.86			Total Rate =	139616.61
														Rate per m3	9307.77

RATE ANALYSIS (2082/083)

Description of works:	Providing and laying of Machine mixed Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M15 (Including Formwork)	Unit : 15 m3
Spec. cl. No: 2000		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
20.2 A	Skilled	md	3.00	1215.00	3645.00	cement	mt	4.130	13500.00	55755.00	mixer (0.28/ 0.20 m^3)	hr	6.00	826.26	4957.56
	Unskilled	md	30.00	855.00	25650.00	aggregate 40mm	m^3	8.100	1990.00	16119.00	Generator	hr	6.00	1173.44	7040.64
						aggregate 20mm	m^3	4.050	1990.00	8059.50	Mix Design and Quality Control		0.00	of Cost of concrete	0.00
						aggregate 10mm	m^3	1.350	2044.00	2759.40					
						Coarse Sand	m^4	6.750	2329.00	15720.75					
						water	lit	2000.000	0.19	385.00					
				Sub total of A =	29295.00				Sub total of B =	98798.65				Sub total of C =	11998.20
				Sub total of A +B + C =	140091.85	Formwork @ 4 % of A+B+C		5603.674	Contractor's overhead expenses 15% =		21854.33			Total Rate =	167549.85
														Rate per m3	11169.99

Description of works:	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M15 (Including Formwork) Manual	Unit : 15 m3
Spec. cl. No: 2000		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
20.2 A	Skilled	md	4.50	1215.00	5467.50	cement	mt	4.130	13500.00	55755.00					
	Unskilled	md	45.00	855.00	38475.00	aggregate 40mm	m^3	8.100	1990.00	16119.00					
						aggregate 20mm	m^3	4.050	1990.00	8059.50					
						aggregate 10mm	m^3	1.350	2044.00	2759.40					
						Coarse Sand	m^4	6.750	2329.00	15720.75					
						water	lit	2000.000	0.19	385.00					
				Sub total of A =	43942.50				Sub total of B =	98798.65				Sub total of C =	0.00
				Sub total of A +B + C =	142741.15	Formwork @ 4 % of A+B+C		5709.646	Contractor's overhead expenses 15% =		22267.62			Total Rate =	170718.42
														Rate per m3	11381.23

Description of works:	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. PCC Grade M20 (Including Formwork)	Unit : 15 m3
Spec. cl. No: 2000		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
20.2 B	Skilled	md	3.00	1215.00	3645.00	cement	mt	5.160	13500.00	69660.00	mixer (0.28/ 0.20 m^3)	hr	6.00	826.26	4957.56
	Unskilled	md	30.00	855.00	25650.00	aggregate 40mm	m^3	5.400	1990.00	10746.00	Generator	hr	6.00	1173.44	7040.64
						aggregate 20mm	m^3	5.400	1990.00	10746.00					
						aggregate 10mm	m^3	2.700	2044.00	5518.80					
						Coarse Sand	m^4	6.750	2329.00	15720.75					
						water	lit	2500.000	0.19	481.25					
				Sub total of A =	29295.00				Sub total of B =	112872.80				Sub total of C =	11998.20
				Sub total of A +B + C =	154166.00	Formwork @ 4 % of A+B+C		6166.64	Contractor's overhead expenses 15% =		24049.90			Total Rate =	184382.54
														Rate per m3	12292.17

RATE ANALYSIS (2082/083)

Description of works:	Providing and laying of Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications.RCC Grade M20 (Including Formwork)	Unit : 15 m3
Spec. cl. No: 2000		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
20.2 C	Skilled	md	3.00	1215.00	3645.00	cement	mt	5.210	13500.00	70335.00	mixer (0.28/ 0.20 m^3)	hr	6.00	826.26	4957.56
	Unskilled	md	30.00	855.00	25650.00	aggregate 20mm	m^3	8.100	1990.00	16119.00	Generator	hr	6.00	1173.44	7040.64
						aggregate 10mm	m^3	5.400	2044.00	11037.60					
						Coarse Sand	m^4	6.750	2329.00	15720.75					
						water	lit	2500.000	0.19	481.25					
				Sub total of A =	29295.00				Sub total of B =	113693.60				Sub total of C =	11998.20
				Sub total of A +B + C =	154986.80	Formwork @ 4 % of A+B+C		6199.472	Contractor's overhead expenses 15% =		24177.94			Total Rate =	185364.21
														Rate Per 1m3	12357.61

Description of works:	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. PCC Grade M25 (Including Formwork)	Unit : 15 m3
Spec. cl. No: 2000		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
20.2 D	Skilled	md	3.00	1215.00	3645.00	cement	mt	5.990	13500.00	80865.00	mixer (0.28/ 0.20 m^3)	hr	6.00	826.26	4957.56
	Unskilled	md	30.00	855.00	25650.00	aggregate 40mm	m^3	5.400	1990.00	10746.00	Generator	hr	6.00	1173.44	7040.64
						aggregate 20mm	m^3	5.400	2044.00	11037.60					
						aggregate 10mm	m^3	2.700	2044.00	5518.80					
						Coarse Sand	m^4	6.750	2329.00	15720.75					
						water	lit	3000.000	0.19	577.50					
				Sub total of A =	29295.00				Sub total of B =	124465.65				Sub total of C =	11998.20
				Sub total of A +B + C =	165758.85	Formwork @ 3.75 % of A+B+C		6215.956875	Contractor's overhead expenses 15% =		25796.22			Total Rate =	197771.03
														Rate per m3	13184.74

RATE ANALYSIS (2082/083)

Description of works:	Providing and laying of Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. RCC Grade M25 (Including Formwork)	Unit : 15 m3
Spec. cl. No: 2000		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
20.2 E	Skilled	md	3.00	1215.00	3645.00	cement	mt	6.050	13500.00	81675.00	mixer (0.28/ 0.20 m^3)	hr	6.00	826.26	4957.56
	Unskilled	md	30.00	855.00	25650.00	aggregate 20mm	m^3	8.100	1990.00	16119.00	Generator	hr	6.00	1173.44	7040.64
						aggregate 10mm	m^3	5.400	2044.00	11037.60					
						Coarse Sand	m^4	6.750	2329.00	15720.75					
						water	lit	3000.000	0.19	577.50					
						Admixture @ 0.4 % of Cement	KG	24.200	288.00	6969.60					
				Sub total of A =	29295.00				Sub total of B =	132099.45				Sub total of C =	11998.20
				Sub total of A +B + C =	173392.65	Formwork @ 3.75 % of A+B+C		6502.22	Contractor's overhead expenses 15% =		26984.23			Total Rate =	206879.11
														Rate Per 1m3	13791.94

Description of works:	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. PCC Grade M30 (Including Formwork)	Unit : 15 m3
Spec. cl. No: 2000		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
20.2 F	Skilled	md	3.00	1215.00	3645.00	cement	mt	6.080	13500.00	82080.00	mixer (0.28/ 0.20 m^3)	hr	6.00	826.26	4957.56
	Unskilled	md	30.00	855.00	25650.00	aggregate 40mm	m^3	5.400	1990.00	10746.00	Generator	hr	6.00	1173.44	7040.64
						aggregate 20mm	m^3	5.400	2044.00	11037.60					
						aggregate 10mm	m^3	2.700	2044.00	5518.80					
						Coarse Sand	m^4	6.750	2329.00	15720.75					
						water	lit	3000.000	0.19	577.50					
				Sub total of A =	29295.00				Sub total of B =	125680.65				Sub total of C =	11998.20
				Sub total of A +B + C =	166973.85	Formwork @ 3.5 % of A+B+C		5844.08	Contractor's overhead expenses 15% =		25922.69			Total Rate =	198740.62
														Rate per m3	13249.37

Description of works:	Providing and laying of Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. RCC Grade M30 (Including Formwork)	Unit : 15 m3
Spec. cl. No: 2000		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
20.2 G	Skilled	md	3.00	1215.00	3645.00	cement	mt	6.100	13500.00	82350.00	mixer (0.28/ 0.20 m^3)	hr	6.00	826.26	4957.56
	Unskilled	md	30.00	855.00	25650.00	aggregate 20mm	m^3	8.100	1990.00	16119.00	Generator	hr	6.00	1173.44	7040.64
						aggregate 10mm	m^3	5.400	2044.00	11037.60					
						Coarse Sand	m^4	6.750	2329.00	15720.75					
						water	lit	3000.000	0.19	577.50					
						Admixture @ 0.4 % of Cement	KG	24.400	288.00	7027.20					
				Sub total of A =	29295.00				Sub total of B =	132832.05				Sub total of C =	11998.20
				Sub total of A +B + C =	174125.25	Formwork @ 3.5 % of A+B+C		6094.38	Contractor's overhead expenses 15% =		27032.95			Total Rate =	207252.58
														Rate Per 1m3	13814.84