RATE ANALYSIS (2082/083)

Description of works:	Providing and laying of Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. RCC Grade M35 (Including Formwork)														Unit : 15 m3
Spec. cl. No: 2000															
Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
20.2 H	Skilled	md	3.00	1215.00	3645.00	cement	mt	6.330	13500.00	85455.00	mixer (0.28/ 0.20 m^3)	hr	6.00	826.26	4957.56
	Unskilled	md	30.00	855.00	25650.00	aggregate 20mm	m^3	8.100	1990.00	16119.00	Generator	hr	6.00	1173.44	7040.64
						aggregate 10mm	m^3	5.400	2044.00	11037.60					
						Coarse Sand	m^4	6.750	2329.00	15720.75					
						water	lit	3000.000	0.19	577.50					
						Admixture @ 0.4 % of Cement	KG	25.320	288.00	7292.16					
				Sub total of A =	29295.00				Sub total of B =	136202.01				Sub total of C =	11998.20
				Sub total of A +B + C =	177495.21	Formwork @ 3 % of A+B+C		5324.8563	Contractor's overhead expenses 15% =		27423.01			Total Rate =	210243.08
														Rate Per 1m3	14016.21

Description of works:	Providing and laying of Reinforced Cement Concrete in Sub-structure complete as per Drawing and Technical Specifications. RCC Grade M20 Height upto 5 m (Including Formwork)														Unit : 15 m3
Spec. cl. No: 2000															
Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
20.4 E(P)	Skilled	md	3.00	1215.00	3645.00	cement	mt	5.210	13500.00	70335.00	mixer (0.28/ 0.20 m^3)	hr	6.00	826.26	4957.56
	Unskilled	md	30.00	855.00	25650.00	aggregate 20mm	m^3	8.100	1990.00	16119.00	Generator	hr	6.00	1173.44	7040.64
						aggregate 10mm	m^3	5.400	2044.00	11037.60					
						Coarse Sand	m^4	6.750	2329.00	15720.75					
						water	lit	2500.000	0.19	481.25					
				Sub total of A =	29295.00				Sub total of B =	113693.60				Sub total of C =	11998.20
				Sub total of A +B + C =	154986.80	Formwork @ 10 % of A+B+C		15498.68	Contractor's overhead expenses 15% =		25572.82			Total Rate =	196058.30
														Rate Per 1m3	13070.55

RATE ANALYSIS (2082/083)

Description of works:	Providing and laying of Reinforced Cement Concrete in Sub-structure complete as per Drawing and Technical Specifications. RCC Grade M20 Height above 5 to 10m (Including Formwork)	Unit : 15 m3
Spec. cl. No: 2000		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
20.4 E(q)	Skilled	md	3.00	1215.00	3645.00	cement	mt	5.210	13500.00	70335.00	mixer (0.28/ 0.20 m^3)	hr	6.00	826.26	4957.56
	Unskilled	md	30.00	855.00	25650.00	aggregate 20mm	m^3	8.100	1990.00	16119.00	Generator	hr	6.00	1173.44	7040.64
						aggregate 10mm	m^3	5.400	2044.00	11037.60					
						Coarse Sand	m^4	6.750	2329.00	15720.75					
						water	lit	2500.000	0.19	481.25					
				Sub total of A =	29295.00	Formwork @ 12% of A+B+C		18598.416	Sub total of B =	113693.60				Sub total of C =	11998.20
				Sub total of A +B + C =	154986.80	To cater for extra lift @2% of A+B+C		3099.736	Contractor's overhead expenses 15% =		26502.74			Total Rate =	203187.69
														Rate Per 1m3	13545.85

Description of works:	Providing and laying of Reinforced Cement Concrete in Sub-structure complete as per Drawing and Technical Specifications. Grade M25 Height upto 5 m (Including Formwork)	Unit : 15 m3
Spec. cl. No: 2000		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
20.4 F(p)	Skilled	md	3.00	1215.00	3645.00	cement	mt	6.050	13500.00	81675.00	mixer (0.28/ 0.20 m^3)	hr	6.00	826.26	4957.56
	Unskilled	md	30.00	855.00	25650.00	aggregate 20mm	m^3	8.100	1990.00	16119.00	Generator	hr	6.00	1173.44	7040.64
						aggregate 10mm	m^3	5.400	2044.00	11037.60					
						Coarse Sand	m^4	6.750	2329.00	15720.75					
						water	lit	3000.000	0.19	577.50					
						Admixture @ 0.4 % of Cement	KG	24.200	288.00	6969.60					
				Sub total of A =	29295.00				Sub total of B =	132099.45				Sub total of C =	11998.20
				Sub total of A +B + C =	173392.65	Formwork @ 10% of A+B+C		17339.27	Contractor's overhead expenses 15% =		28609.79			Total Rate =	219341.70
														Rate Per 1m3	14622.78

RATE ANALYSIS (2082/083)

Description of works:	Providing and laying of Reinforced Cement Concrete in Sub-structure complete as per Drawing and Technical Specifications. RCC Grade M25 Height Above 5m to 10m (Including Formwork).	Unit : 15 m3
Spec. cl. No: 2000		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
20.4 F(q)	Skilled	md	3.00	1215.00	3645.00	cement	mt	6.050	13500.00	81675.00	mixer (0.28/ 0.20 m^3)	hr	6.00	826.26	4957.56
	Unskilled	md	30.00	855.00	25650.00	aggregate 20mm	m^3	8.100	1990.00	16119.00	Generator	hr	6.00	1173.44	7040.64
						aggregate 10mm	m^3	5.400	2044.00	11037.60					
						Coarse Sand	m^4	6.750	2329.00	15720.75					
						water	lit	3000.000	0.19	577.50					
						Admixture @ 0.4 % of Cement	KG	24.200	288.00	6969.60					
				Sub total of A =	29295.00	Formwork @ 12% of A+B+C		20807.12	Sub total of B =	132099.45				Sub total of C =	11998.20
				Sub total of A +B + C =	173392.65	To cater for extra lift @2% of A+B+C		3467.85	Contractor's overhead expenses 15% =		29650.14			Total Rate =	227317.76
														Rate Per 1m3	15154.52

Description of works:	Providing and laying of Reinforced Cement Concrete in Sub-structure complete as per Drawing and Technical Specifications. RCC Grade M30 Height upto 5 m (Including Formwork)	Unit : 15 m3
Spec. cl. No: 2000		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
20.4 G (p)	Skilled	md	3.00	1215.00	3645.00	cement	mt	6.100	13500.00	82350.00	mixer (0.28/ 0.20 m^3)	hr	6.00	826.26	4957.56
	Unskilled	md	30.00	855.00	25650.00	aggregate 20mm	m^3	8.100	1990.00	16119.00	Generator	hr	6.00	1173.44	7040.64
						aggregate 10mm	m^3	5.400	2044.00	11037.60					
						Coarse Sand	m^4	6.750	2329.00	15720.75					
						water	lit	3000.000	0.19	577.50					
						Admixture @ 0.4 % of Cement	KG	24.400	288.00	7027.20					
				Sub total of A =	29295.00				Sub total of B =	132832.05				Sub total of C =	11998.20
				Sub total of A +B + C =	174125.25	Formwork @10 % of A+B+C		17412.53	Contractor's overhead expenses 15% =		28730.67			Total Rate =	220268.44
														Rate Per 1m3	14684.56

RATE ANALYSIS (2082/083)

Description of works:	Providing and laying of Reinforced Cement Concrete in Sub-structure complete as per Drawing and Technical Specifications. Grade M30 Height above 5 m to 10m(including formworks)	Unit : 15 m3
Spec. cl. No: 2000		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
20.4 G (q)	Skilled	md	3.00	1215.00	3645.00	cement	mt	6.100	13500.00	82350.00	mixer (0.28/ 0.20 m^3)	hr	6.00	826.26	4957.56
	Unskilled	md	30.00	855.00	25650.00	aggregate 20mm	m^3	8.100	1990.00	16119.00	Generator	hr	6.00	1173.44	7040.64
						aggregate 10mm	m^3	5.400	2044.00	11037.60					
						Coarse Sand	m^4	6.750	2329.00	15720.75					
						water	lit	3000.000	0.19	577.50					
						Admixture @ 0.4 % of Cement	KG	24.400	288.00	7027.20					
				Sub total of A =	29295.00	Formwork @12 % of A+B+C		20695.03	Sub total of B =	132832.05				Sub total of C =	11998.20
				Sub total of A +B + C =	174125.25	To cater for extra lift @2% of A+B+C		3482.505	Contractor's overhead expenses 15% =		29775.42			Total Rate =	228278.20
														Rate Per 1m3	15218.55

Description of works:	Providing and placing machine mixed M25/20 cement concrete for superstructure, deckslab, girder, etc. including compaction, curing, testing and lead 30m. etc. all complete as per specification and drawing.	Unit : 1 m3
Spec. cl. No: 2000		

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
20.03.a.ii	Skilled	md	1.00	1215.00	1215.00	cement	mt	0.375	13500.00	5062.50	mixer (0.28/ 0.20 m^3)	hr	0.60	826.260	495.75
	Unskilled	md	6.00	855.00	5130.00	aggregate 10-20mm	m^3	0.580	1940.00	1125.20	vibrator	hr	0.25	2626.110	656.52
						aggregate 10mm & down	m^3	0.300	2044.00	613.20	Mix Design and Quality Control		0.03	of Cost of concrete	394.91
						coarse sand	m^3	0.450	2329.00	1048.05					
						petrol	lit	0.100	141.59	14.15					
						diesel	lit	3.000	130.97	392.92					
						water	lit	225.000	0.19	43.31					
				Sub total of A =	6345.00				Sub total of B =	8299.33				Sub total of C =	1547.18
				Sub total of A +B + C =	16191.51				Contractor's overhead expenses 15% =		2428.73			Unit Rate =	18620.24

RATE ANALYSIS (2082/083)

Description of works: Providing and laying , fitting and placing HYSD bar reinforcement in sub-structure complete as per Drawing and Technical Specifications

Spec. cl. No: 2014

Unit : 1 ton.

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
20.5	Skilled	md	4.00	1215.00	4860.00	Reinforcement	t	1.100	91000.00	100100.00					
	Unskilled	md	9.00	855.00	7695.00	Binding wire	kg	8.000	111.00	888.00					
				Sub total of A =	12555.00				Sub total of B =	100988.00				Sub total of C =	0.00
				Sub total of A +B + C =	113543.00				Contractor's overhead expenses 15% =		17031.45			Unit Rate =	130574.45
														Rate Per KG	130.57

Description of works: Providing and laying of Reinforced / Pre-stressed Cement Concrete in Solid slab Super Structure as per Drawing and Technical Specifications. RCC Grade M20 Height upto 5m (including formworks)

Spec. cl. No: 2000

Unit : 15 m3

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
20.8 A (i) (p)	Skilled	md	3.00	1215.00	3645.00	cement	mt	5.120	13500.00	69120.00	mixer (0.28/ 0.20 m^3)	hr	6.00	826.26	4957.56
	Unskilled	md	30.00	855.00	25650.00	Coarse Sand	m^3	6.750	2329.00	15720.75	Generator	hr	6.00	1173.44	7040.64
						aggregate 20mm	m^3	8.100	1990.00	16119.00					
						aggregate 10mm	m^3	5.400	2044.00	11037.60					
						water	lit	3000.000	0.19	577.50					
				Sub total of A =	29295.00	Formwork & Staging @20 % of A+B+C		30773.61	Sub total of B =	112574.85				Sub total of C =	11998.20
				Sub total of A +B + C =	153868.05				Contractor's overhead expenses 15% =		27696.25			Total Rate =	212337.91
														Rate Per 1m3	14155.86