RATE ANALYSIS (2082/083)

						aggregate 10mm	m^3	2.700	2044.00	5518.80					
						Coarse Sand	m^4	6.750	2329.00	15720.75					
						water	lit	2500.000	0.19	481.25					
					Sub total of A =	29295.00				Sub total of B =	112872.80			Sub total of C =	11998.20
					Sub total of A +B + C =	154166.00				Contractor's overhead expenses 15% =	23,124.90			Total Rate =	177290.900
														Rate per m3	11819.39

Description of works: Providing and laying of Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications.RCC Grade M20 (Excluding Formwork) — **Unit : 15 m3**

Spec. cl. No: 2000

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
20.2 C	Skilled	md	3.00	1215.00	3645.00	cement	mt	5.210	13500.00	70335.00	mixer (0.28/ 0.20 m^3)	hr	6.00	826.26	4957.56
	Unskilled	md	30.00	855.00	25650.00	aggregate 20mm	m^3	8.100	1990.00	16119.00	Generator	hr	6.00	1173.44	7040.64
						aggregate 10mm	m^3	5.400	2044.00	11037.60					
						Coarse Sand	m^4	6.750	2329.00	15720.75					
						water	lit	2500.000	0.1925	481.25					
					Sub total of A =	29295.00				Sub total of B =	113693.60			Sub total of C =	11998.20
					Sub total of A +B + C =	154986.80				Contractor's overhead expenses 15% =	23,248.02			Total Rate =	178234.82
														Rate Per 1m3	11882.32

Description of works: Collection of Stone from near by site/source and laying of hand pack Stone soling and packing with smaller stone on prepared surface as per Drawing and Technical Specifications. — **Unit : 5 m3**

Spec. cl. No: 1006

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
	Unskilled	md	0.00	855.00	0.00	Stone	m^3	6.00	1232.91	7397.46					
	Skilled	md	6.00	1215.00	7290.00										
					Sub total of A =	7290.00				Sub total of B =	7397.46			Sub total of C =	0.00
					Sub total of A +B + C =	14687.46				Contractor's overhead expenses 15% =	2,203.12			Unit Rate :	16890.579
														Rate Per M3	3378.12

Description of works: Collection of stone from near by site/source and laying Random rubble stone masonry in cement mortar [cement(1) : sand(4)] in Foundation complete as per drawing and technical specification. Manual Mixed Mortar — **Unit : 5 m3**

Spec. cl. No: 2602,2603,2607

Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
26.3.b	Skilled	md	7.00	1215.00	8505.00	Cement	t	0.620	13500.00	8370.00	Concrete mixer or other tools 5 % of L C		0.05	of L.C.	1023.75
	Unskilled	md	14.00	855.00	11970.00	Sand	m^3	1.740	2329.00	4052.46					
						Stone	m^3	5.750	1232.91	7089.23					
						water	lit	1000.00	0.1925	192.50					
					Sub total of A =	20475.00				Sub total of B =	19704.19			Sub total of C =	1023.75
					Sub total of A +B + C =	41202.94				Contractor's overhead expenses 15% =	6,180.44			Rate per 5 m3 =	47383.3810
														Rate Per m3=	9476.68

RATE ANALYSIS (2082/083)

Description of works: Collection of stone from near by site/source and laying Random rubble stone masonry in cement mortar [cement(1) : sand(4)] in Foundation complete as per drawing and technical specification. Machine Mixed Mortar — **Unit : 5 m3**

Spec. cl. No: 2602,2603,2607

Norms No.	Labour (A) Type	Unit	Qty.	Rate	Amount	Material (B) Type	Unit	Qty.	Rate	Amount	Equipment (C) Type	Unit	Qty.	Rate	Amount
26.3.b	Skilled	md	7.00	1215.00	8505.00	Cement	t	0.620	13500.00	8370.00	Concrete mixer	hr	0.75	826.26	619.70
	Unskilled	md	9.00	855.00	7695.00	Sand	m^3	1.740	2329.00	4052.46					
						Stone	m^3	5.750	1232.91	7089.23					
						water	lit	1000.00	0.19	192.50					
				Sub total of A =	16200.00				Sub total of B =	19704.19				Sub total of C =	619.70
				Sub total of A +B + C =	36523.89				Contractor 's overhead expenses 15%		5478.58			Rate per 5 m3 =	**42002.47**
														Rate Per m3=	**8400.49**

Description of works: Collection of stone from near by site/source and laying Random rubble stone masonry in cement mortar [cement(1) : sand(6)] in Foundation complete as per drawing and technical specification. — **Unit : 5 m3**

Spec. cl. No: 2602,2603,2607

Norms No.	Labour (A) Type	Unit	Qty.	Rate	Amount	Material (B) Type	Unit	Qty.	Rate	Amount	Equipment (C) Type	Unit	Qty.	Rate	Amount
26.3.C	Skilled	md	7.00	1215.00	8505.00	Cement	t	0.450	13500.00	6075.00					
	Unskilled	md	14.00	855.00	11970.00	Sand	m^3	2.080	2329.00	4844.32					
						Stone	m^3	5.750	1232.91	7089.23					
						water	lit	1000.00	0.1925	192.50					
				Sub total of A =	20475.00				Sub total of B =	18201.05				Sub total of C =	0.00
				Sub total of A +B + C =	38676.05				Contractor 's overhead expenses 15%		5801.41			Rate per 5 m3 =	**44477.46**
														Rate Per m3=	**8895.49**

Description of works: Collection of stone from near by site/source and laying Random rubble stone masonry in cement mortar [cement(1) : sand(4)] in Structure complete as per drawing and technical specification — **Unit : 5 m3**

Spec. cl. No: 2600, 2607

Norms No.	Labour (A) Type	Unit	Qty.	Rate	Amount	Material (B) Type	Unit	Qty.	Rate	Amount	Equipment (C) Type	Unit	Qty.	Rate	Amount
26.5 A	Skilled	md	7.00	1215.00	8505.00	Cement	t	0.660	13500.00	8910.00	Scaffolding 5 % of L C and MC		0.05	of L.C.	2305.27
	Unskilled	md	20.00	855.00	17100.00	Sand	m^3	1.850	2329.00	4308.65					
						Stone	m^3	5.750	1232.91	7089.23					
						water	lit	1000.00	0.1925	192.50					
				Sub total of A =	25605.00				Sub total of B =	20500.38				Sub total of C =	2305.27
				Sub total of A +B + C =	48410.65				Contractor 's overhead expenses 15%		7261.60			Rate per 5 m3 =	**55672.25**
														Rate Per m3=	**11134.45**

Description of works: Collection of stone from near by site/source and laying Random rubble stone masonry in cement mortar [cement(1) : sand(6)] in Structure complete as per drawing and technical specification — **Unit : 5 m3**

Spec. cl. No: 2600, 2607

Norms No.	Labour (A) Type	Unit	Qty.	Rate	Amount	Material (B) Type	Unit	Qty.	Rate	Amount	Equipment (C) Type	Unit	Qty.	Rate	Amount
26.6 A	Skilled	md	7.00	1215.00	8505.00	Cement	t	0.480	13500.00	6480.00	Scaffolding 5 % of L C and M C		0.05	of L.C.	2198.91
	Unskilled	md	20.00	855.00	17100.00	Sand	m^3	1.980	2329.00	4611.42					
						Stone	m^3	5.750	1232.91	7089.23					
						water	lit	1000.00	0.1925	192.50					

RATE ANALYSIS (2082/083)

				Sub total of A =	25605.00				Sub total of B =	18373.15				Sub total of C =	2198.91
				Sub total of A +B + C =	46177.06				Contractor 's overhead expenses 15%		6926.56			0	53103.62
														Rate per m3	10620.72
Description of works:						Collection of Stone from near by site/source and laying Plum Concrete (Boulder Mixed Concrete) as per Drawing and Specifications 60% M15 concrete and 40% boulders/stone using Mechanical Means.										Unit : 10 m3
Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
24.21 C	Skilled	md	3.00	1215.00	3645.00	cement	mt	1.700	13500.00	22950.00	mixer (0.28/ 0.20 m^3)	hr	6.00	826.26	4957.56
	Unskilled	md	30.00	855.00	25650.00	aggregate(20- 40)mm	m^3	3.450	1990.00	6865.50	Concrete Vibrator	hr	6.00	214	1284.00
						aggregate (10-20)mm	m^3	1.560	1990.00	3104.40					
						aggregate(5-10)mm	m^3	0.720	2044.00	1471.68					
						Sand	m^3	3.000	2329.00	6987.00					
						Boulder Stone	m^3	4.400	1232.91	5424.80					
				Sub total of A =	29295.00				Sub total of B =	46803.38				Sub total of C =	6241.56
				Sub total of A +B + C+d =	82339.94				Contractor 's overhead expenses 15%		12350.99			Total Rate =	94690.93
														Rate per m3	9469.09
Description of works: Spec. cl. No: 2402						Provide mechanically woven double twisted crates/mattress including rolling cutting and with lacing wire and binding wire as per specification										Unit : 1 Sqm
Norms No. 24.2	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
						Machine made gabion	sqm	1.00	310.20	310.20					
				Sub total of A =	0.00				Sub total of B =	310.20				Sub total of C =	0.00
				Sub total of A +B + C =	310.20				Contractor 's overhead expenses 15%		46.53			Unit Rate =	356.73
Description of works: Spec. cl. No: 2401						Assembling mechanically woven gabion boxes/ mattresses placing in position including streching forming compartments, tying the sides and diapharagm with binding wire in each mesh tying the bracing wire and tie wires and tying down the lid complete as per specification										Unit : 160 sqm
Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
24.3	Skilled	md	2.00	1215.00	2430.00										
	Unskilled	md	10.00	855.00	8550.00										
				Sub total of A =	10980.00				Sub total of B =	0.00				Sub total of C =	0.00
				Sub total of A +B + C =	10980.00				Contractor 's overhead expenses 15%		1647.00			Unit Rate =	12627.00
														Rate per m2	78.92
Description of works: Spec. cl. No: 2401						Collection of stone from near by side/source and filling stone/ boulder in gabion boxes/ mattresses etc including dressing, bedding, bonding all complete as per drawing and technical specification										Unit : 10 m3
Norms No.	Labour (A)					Material (B)					Equipment (C)				
	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount	Type	Unit	Qty.	Rate	Amount
24.4	Skilled	md	2.00	1215.00	2430.00	Boulder/Stone	m3	11.00	1232.91	13562.01					
	Unskilled	md	8.00	855.00	6840.00										
				Sub total of A =	9270.00				Sub total of B =	13562.01				Sub total of C =	0.00
				Sub total of A +B + C =	22832.01				Contractor 's overhead expenses 15%		3424.80			Unit Rate =	26256.81

RATE ANALYSIS (2082/083)

														Rate per m3	2625.68
24.3	**Supply of machine made hexagonal mesh type 100mm x 120 mm Gabion boxes / mattresses with diapharagms, with binding wire 12 swg, mesh wire 3mm and selvedged wire 3.9 mm and lacing wire 2.4 mm, including palcing in position including stretching, forming compartments; tying with bracing wires and tie wires; tying down the lid complete; and collection of stone from nearby side /source and filling stone / boulder in gabion boxes / mattresses etc. including dressing, beding, bonding and all transporation as per specification.**														**Unit : 1 m3**
	Box size			**Unit**	**Sqm**	**Filling Cum**	**Supply of box**		**Assembling**	**Filling**	**Total**	**Per m3**			
	1.5 x 1 x 1				8	1.50	2853.84		631.35	3938.52	**7423.71**	**4949.14**			
	2 x 1 x 1				11	2.00	3924.03		868.11	5251.36	**10043.50**	**5021.75**			
	3 x 1 x 1				16	3.00	5707.68		1262.70	7877.04	**14847.42**	**4949.14**			
									Average per m3			**4973.34**		**4973.34**	
Description of works:	**Providing and filling stone/ boulder in gabion boxes/ mattresses etc including dressing, bedding, bonding all complete as per drawing and technical specification**														**Unit : 10 m3**
Spec. cl. No: 2401															
Norms No.	**Labour (A)**					**Material (B)**					**Equipment (C)**				
	Type	**Unit**	**Qty.**	**Rate**	**Amount**	**Type**	**Unit**	**Qty.**	**Rate**	**Amount**	**Type**	**Unit**	**Qty.**	**Rate**	**Amount**
24.4	Skilled	md	2.00	1215.00	2430.00	Boulder/Stone	m3	11.00	1232.91	13562.01					
	Unskilled	md	8.00	855.00	6840.00										
				Sub total of A =	9270.00				Sub total of B =	13562.01				Sub total of C =	0.00
				Sub total of A +B + C =	22832.01	Contractor 's overhead expenses 15%					3424.80			Unit Rate =	26256.81
														Rate per m3	**2625.68**
Description of works:	**Painting Two Coats on Concrete Surfaces Providing and Painting two coats after filling the surface with synthetic enamel paint in all shades on concrete / plaster surfaces as per Drawing and Technical Specifications.**														**Unit : 10 m2**
Spec. cl. No: 1501															
Norms No.	**Labour (A)**					**Material (B)**					**Equipment (C)**				
	Type	**Unit**	**Qty.**	**Rate**	**Amount**	**Type**	**Unit**	**Qty.**	**Rate**	**Amount**	**Type**	**Unit**	**Qty.**	**Rate**	**Amount**
15.4	Skilled	md	3.00	1215.00	3645.00	Paint	lit	6.00	478.74	2872.44					
	Unskilled	md	2.00	855.00	1710.00										
				Sub total of A =	5355.00				Sub total of B =	2872.44				Sub total of C =	0.00
				Sub total of A +B + C =	8227.44	Contractor 's overhead expenses 15%					1234.12			Unit Rate =	9461.56
														Rate per m3	**946.16**
Description of works:	**Lettering new Letter and Figures of any Shade Providing and lettering new letter and figures of any shade with synthetic enamel paint black or any other approved color to give an even shade.**														**Unit : 1600 cm-letter**
Spec. cl. No: 1506															
Norms No.	**Labour (A)**					**Material (B)**					**Equipment (C)**				
	Type	**Unit**	**Qty.**	**Rate**	**Amount**	**Type**	**Unit**	**Qty.**	**Rate**	**Amount**	**Type**	**Unit**	**Qty.**	**Rate**	**Amount**
15.8	Skilled	md	4.00	1215.00	4860.00	Paint	lit	0.70	478.74	335.11					
	Unskilled	md	2.00	855.00	1710.00										
				Sub total of A =	6570.00				Sub total of B =	335.11				Sub total of C =	0.00
				Sub total of A +B + C =	6905.11	Contractor 's overhead expenses 15%					1035.77			Unit Rate =	7940.88
														Rate per cm-letter	**4.96**
											100 letter for 16 cm ht.=1600cm-letter				